

NOTE: VIEW 1 IS TOP VIEW IN PLAN DRAWINGS, VIEW 2 IS BOTTOM VIEW IN PLAN DRAWINGS

PAVEMENT MARKING REMOVAL – GRINDING (CODE NUMBER X0327979)									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	DESCRIPTION	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL LENGTH	MULTIPLIER*	AREA (SQ FT)
SHEET 21	GORE AREA	98+05.77	99+00.00	47.78	50.32	L	36.68	1.00	36.68
VIEW 1	GORE AREA	98+29.17	98+53.18	51.83	56.25	R	24.01	1.00	24.01
	GORE AREA	99+00.00	99+25.77	50.32	52.00	L	19.34	1.00	19.34
	DIAGONAL SHOULDER STRIPES	99+97.13	104+64.41	45.80	56.70	L	54.41	1.00	54.41
	DIAGONAL SHOULDER STRIPES	100+00.86	101+60.34	61.80	57.60	R	43.51	1.00	43.51
	4" SOLID EDGE LINE	101+01.34	102+94.69	206.75	63.41	R	246.24	0.33	82.08
	4" SOLID EDGE LINE	101+04.00	105+16.75	45.79	47.22	L	412.75	0.33	137.58
	4" SKIP DASH	101+04.00	113+75.00	33.61	34.73	L	1271.00	0.0833	105.91
	4" SKIP DASH	101+04.00	113+75.00	21.61	22.73	L	1271.00	0.0833	105.91
	4" SOLID EDGE LINE	101+04.00	113+75.00	9.77	10.73	L	1271.00	0.33	423.67
	4" SOLID EDGE LINE	101+04.00	113+75.00	9.70	9.27	R	1271.00	0.33	423.67
	4" SKIP DASH	101+04.00	113+75.00	21.26	21.27	R	1271.00	0.0833	105.91
	4" SKIP DASH	101+04.00	113+75.00	33.26	33.27	R	1271.00	0.0833	105.91
	4" SOLID EDGE LINE	101+04.00	102+93.21	45.58	44.87	R	189.21	0.33	63.07
	4" SOLID EDGE LINE	101+14.87	113+75.00	216.58	45.27	R	1311.41	0.33	437.14
	4" SOLID EDGE LINE	102+24.11	105+16.60	259.20	69.82	L	366.49	0.33	122.16
	4" SOLID EDGE LINE	102+28.05	113+75.00	285.28	46.73	L	1230.46	0.33	410.15
	8" SOLID EDGE LINE	102+93.21	106+93.06	44.87	45.23	R	399.85	0.66	263.90
	8" SOLID EDGE LINE	102+94.69	106+93.06	63.41	45.23	R	339.31	0.66	223.94
	GORE AREA	103+15.65	105+55.53	51.69	46.47	R	87.94	1.00	87.94
	DIAGONAL SHOULDER STRIPES	103+23.41	114+00.00	83.90	49.54	R	109.37	1.00	109.37
	8" SOLID EDGE LINE	105+16.60	109+37.11	69.82	46.54	L	420.51	0.66	277.54
	8" SOLID EDGE LINE	105+16.75	109+37.11	47.22	46.54	L	420.36	0.66	277.44
	GORE AREA	105+29.49	109+02.29	68.76	47.76	L	242.98	1.00	242.98
	DIAGONAL SHOULDER STRIPES	106+07.74	112+24.38	82.86	55.31	L	54.71	1.00	54.71
SHEET 22	DIAGONAL SHOULDER STRIPES	114+00.00	115+26.36	49.54	53.41	R	11.72	1.00	11.72
VIEW 1									
SHEET 22	4" SOLID EDGE LINE	100+37.70	101+14.72	331.39	216.47	R	138.44	0.33	46.15
VIEW 2	4" SOLID EDGE LINE	100+72.03	101+01.34	249.43	206.75	R	51.80	0.33	17.09

*MULTIPLIER USED TO CONVERT FROM LINEAR FEET OF MARKING TO SQUARE FEET OF MARKING

PAVEMENT MARKING BLACKOUT TAPE, 5" (CODE NUMBER 70107005)									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	DESCRIPTION	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL LENGTH	MULTIPLIER*	AREA (SQ FT)
REMOVAL SHEETS (21-22)	10' DASH 30' SKIP	86+07.68	101+04.00	22.03	20.89	R	1496.32	0.25	374.08
	4" SOLID EDGE LINE	86+07.77	101+04.00	10.03	9.13	R	1496.23	1.00	1496.23
	10' DASH 30' SKIP	92+67.94	101+04.00	33.93	32.89	R	836.06	0.25	209.02
	4" SOLID EDGE LINE	96+97.66	101+04.00	9.77	10.23	L	406.34	1.00	406.34
	10' DASH 30' SKIP	96+97.67	101+04.00	21.74	22.26	L	406.33	0.25	101.58
	10' DASH 30' SKIP	97+58.67	104+04.00	33.7	34.26	L	645.33	0.25	161.33
	4" SOLID EDGE LINE	98+77.57	101+04.00	45.66	45.31	R	226.43	1.00	226.43
	4" SOLID EDGE LINE	99+40.61	101+40.00	45.79	46.51	L	199.39	1.00	199.39
	10' DASH 30' SKIP	113+75.00	116+86.55	34.73	34.73	L	311.55	0.25	77.89
	10' DASH 30' SKIP	113+75.00	123+71.37	22.73	22.73	L	996.37	0.25	249.09
	4" SOLID EDGE LINE	113+75.00	123+71.37	10.73	10.73	L	996.37	1.00	996.37
	4" SOLID EDGE LINE	113+75.00	116+36.80	45.27	45.27	R	261.80	1.00	261.80

*MULTIPLIER USED TO CONVERT FROM LINEAR FEET OF MARKING TO SQUARE FEET OF MARKING

PAVEMENT MARKING BLACKOUT TAPE, 9" (CODE NUMBER 70107009)									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	DESCRIPTION	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL LENGTH	MULTIPLIER*	AREA (SQ FT)
REMOVAL SHEETS (21-22)	8" EDGE LINE	98+13.72	99+40.61	45.78	45.79	L	126.89	1	126.89
	8" EDGE LINE	98+20.38	98+77.57	45.89	45.66	R	57.19	1	57.19

*MULTIPLIER USED TO CONVERT FROM LINEAR FEET OF MARKING TO SQUARE FEET OF MARKING

DRAINAGE REMOVALS									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	ITEM	CODE NUMBER	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL	
SHEET 21	STORM SEWER REMOVAL 12"	55100500	104+79.50	105+24.27	0.00	0.14	L	45'	
VIEW 2	MEDIAN INLET BOX REMOVAL	X0484300	105+24.27	N/A	0.00	N/A	N/A	1 EACH	

GUARDRAIL REMOVAL (CODE NUMBER 63200310)						
MEASURED FROM NB IL 83 RAMP ALIGNMENT						
DRAWING #	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL LENGTH (FEET)
SHEET 22	32+14.85	36+49.66	10.06	9.85	L	434.81
VIEW 2						

REMOVE EXISTING HANDHOLE (CODE NUMBER 89502380)				
MEASURED FROM IL 83 ALIGNMENT				
DRAWING #	STATION	OFFSET	L/R	QUANTITY (EACH)
SHEET 21	104+47.81	81.54	R	1
VIEW 2				

ROADWAY REMOVALS									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	ITEM	CODE NUMBER	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL	
SHEET 21	PAVEMENT REMOVAL	44000100	104+71.86	105+31.32	VARIES	VARIES	N/A	720 SQ YD	
VIEW 2	PAVED SHOULDER REMOVAL	44004250	102+68.58	104+72.13	229.95	71.02	L	28 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	102+62.95	104+72.06	193.19	71.02	L	28 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	105+31.64	106+52.53	94.32	88.14	L	13 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	100+93.12	104+72.03	55.33	56.76	L	44 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	100+91.99	102+93.19	58.88	56.63	R	24 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	101+10.14	102+94.21	187.53	60.12	R	27 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	101+19.20	103+01.85	219.73	86.30	R	192 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	103+01.85	104+71.73	86.3	73.82	R	19 SQ YD	
	PAVED SHOULDER REMOVAL	44004250	104+71.86	105+31.32	VARIES	VARIES	N/A	328 SQ YD	
	CONCRETE BARRIER REMOVAL, DOUBLE FACE	X4401983	104+72.59	105+31.37	0.00	0.00	N/A	59 FOOT	
	PAVED SHOULDER REMOVAL	44004250	105+31.15	114+50.92	72.89	53.41	R	96 SQ YD	
SHEET 22	PAVED SHOULDER REMOVAL	44004250	114+00.00	114+50.91	53.54	53.27	R	6 SQ YD	
VIEW 1									
SHEET 22	**PAVED SHOULDER REMOVAL	44004250	36+48.84	37+00.00	6.90	5.36	R	33 SQ YD	
VIEW 2									

**MEASURED FROM NB IL 83 RAMP ALIGNMENT

SHORT TERM PAVEMENT MARKING REMOVAL (CODE NUMBER 70300150)									
MEASURED FROM IL 83 ALIGNMENT									
DRAWING #	DESCRIPTION	BEGIN STA	END STA	BEGIN OFFSET	END OFFSET	L/R	TOTAL LENGTH	MULTIPLIER*	AREA (SQ FT)
REMOVAL SHEETS (21-22)	10' DASH 30' SKIP	86+07.68	101+04.00	22.03	20.89	R	1496.32	0.0833	124.64
	4" SOLID EDGE LINE	86+07.77	101+04.00	10.03	9.13	R	1496.23	0.33	493.76
	10' DASH 30' SKIP	92+67.94	101+04.00	33.93	32.89	R	836.06	0.0833	69.64
	4" SOLID EDGE LINE	96+97.66	101+04.00	9.77	10.23	L	406.34	0.33	134.09
	10' DASH 30' SKIP	96+97.67	101+04.00	21.74	22.26	L	406.33	0.0833	33.85
	10' DASH 30' SKIP	97+58.67	104+04.00	33.7	34.26	L	645.33	0.0833	53.76
	8" EDGE LINE	98+13.72	99+40.61	45.78	45.79	R	126.89	0.66	83.75
	8" EDGE LINE	98+20.38	98+77.57	45.89	45.66	R	57.19	0.66	37.75
	4" SOLID EDGE LINE	98+77.57	101+04.00	45.66	45.31	R	226.43	0.33	74.72
	4" SOLID EDGE LINE	99+40.61	101+40.00	45.79	46.51	L	199.39	0.33	65.80
	10' DASH 30' SKIP	113+75.00	116+86.55	34.73	34.73	L	311.55	0.0833	25.95
	10' DASH 30' SKIP	113+75.00	123+71.37	22.73	22.73	L	996.37	0.0833	83.00
	4" SOLID EDGE LINE	113+75.00	123+71.37	10.73	10.73	L	996.37	0.33	328.80
	4" SOLID EDGE LINE	113+75.00	116+36.80	45.27	45.27	R	261.80	0.33	86.39

MODEL: D:\p1\11 - IDOT\040058-01-002 (ENG) - PTB 195-016 Phase II Var Var\Engineering\WO 1 - IL83-IL38500 Drawings\502_CADD_Sheets\1627869-shc-schedule02.dgn
 FILE NAME: P:\040058 - IDOT\040058-01-002 (ENG) - PTB 195-016 Phase II Var Var\Engineering\WO 1 - IL83-IL38500 Drawings\502_CADD_Sheets\1627869-shc-schedule02.dgn



USER NAME = khejtmanek	DESIGNED - KH	REVISED -
PLOT SCALE = 2,0000 ' / in.	CHECKED - AP	REVISED -
PLOT DATE = 3/10/2021	DATE - 3/11/2021	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2020-196-T	DUPAGE	122	17
CONTRACT NO. 62M69				
ILLINOIS FED. AID PROJECT				