

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 90% FED 10% STATE	1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5															
40600300	AGGREGATE (PRIME COAT)	TON	22	22															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	545	545															
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1219	1219															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	10881	10881															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	11701	11701															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4876	4876															
<del>*78000200</del>	<del>THERMOPLASTIC PAVEMENT MARKING LINE 4"</del>	<del>FOOT</del>	<del>25893</del>	<del>25893</del>															
<del>*78004220</del>	<del>PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID LINE 5"</del>	<del>FOOT</del>	<del>11701</del>	<del>11701</del>															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1171	1171															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1171	1171															
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1															
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	59,600	59,600															
*78000815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	238,400	238,400															
*78000845	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH	FOOT	30,500	30,500															
*78000855	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 12 INCH	FOOT	5,200	5,200															
78300100	PAVEMENT MARKING REMOVAL	SQ FT	12,417	12,417															

\* SPECIALTY ITEM

Rev. 5-27-09

FILE NAME =	USER NAME = wlgroendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-55 (STEVENSON EXPRESSWAY) SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cdpw...work\p1201\wlgroendp\0125109-Destgrdn		DRAWN -	REVISED -			55	2007-018I	COOK	14	3	
PLOT SCALE = 100,000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 60C73					
PLOT DATE = 3/14/2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.