

90% FED. / 10% STATE

CODE NO.	ITEM	UNIT	QUANTITIES		
			Y030-1E TOTAL QUANTITY	Y030-1E WILL	Y030-1E COOK
6700040C	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	5	3.75	1.25
67100100	MOBILIZATION	L SUM	1.00	0.75	0.25
80400100	ELECTRIC SERVICE INSTALLATION	EACH	6	4	2
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1.00	0.75	0.25
81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	4	0	4
81700125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	330	0	330
81700130	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 2	FOOT	990	0	990
81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350 MCM	FOOT	1290	940	350
8190C200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1150	840	310
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	353	269	84
82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	8	0	8
83011600	LIGHT POLE, ALUMINUM, 55 FT. M.H., 15 FT. MAST ARM	EACH	4	4	0
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	353	269	84
83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	80	0	80
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	357	273	84
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	10	8	2
84200700	LIGHTING FOUNDATION REMOVAL	EACH	10	8	2
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	0	1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	0	1
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	5	3.75	1.25
X0325702	NIGHT TIME WORK ZONE LIGHTING	L SUM	1.00	0.75	0.25
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1.00	0.75	0.25
X8160395	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600 (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	84725	62800	21925
X8250110	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA	EACH	6	4	2
XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	8	0	8
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL PVC COATED	FOOT	320	0	320
81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL PVC COATED	FOOT	40	0	40
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	1150	840	310
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2330	1620	710
X0326412	INSTALL UNDERGROUND RACEWAY - SPECIAL	FOOT	84725	62800	21925
X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8"	EACH	357	273	84
X8350012	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT.-12	EACH	2	0	2
X8210750	LUMINAIRE, SODIUM VAPOR, RECTILINEAR TYPE, 750 WATT	EACH	4	4	0
<b>2007600 TRAINEES</b>			<b>HOUR</b>	<b>500</b>	<b>500</b>

04080

FILE NAME =	USER NAME = #USER#	DESIGNED	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	COOK/WILL	49	3
		PLOT SCALE = #SCALE#	CHECKED -								CONTRACT NO. 60F84		
		PLOT DATE = #DATE#	DATE -								ILLINOIS FED. AID PROJECT		