

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE									
CODE NO	ITEM	UNIT	URBAN 100% STATE								URBAN 100% STATE										
			TOTAL QUANTITIES	1000							TOTAL QUANTITIES	1000									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	66	66							* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1806	1806						
40600300	AGGREGATE (PRIME COAT)	TON	328	328							* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	452	452						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42	42							* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	292	292						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1							* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	340	340						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	234	234							* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	800	800						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	915	915							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	784	784						
40603515	^{POLYMERIZED} HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,030	8,030							* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1255	1255						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	81,941	81,941							X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	205.6	205.6						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	5444	5444							X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,227	3,227						
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3995	3995																	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	607	607																	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	347	347																	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4690	4690																	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1																	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																	
67100100	MOBILIZATION	L SUM	1	1																	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1																	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5744	5744																	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	317.2	317.2																	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	66244	66244																	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1806	1806																	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	452	452																	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	292	292																	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	340	340																	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	314	314																	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	66244	66244																	

*SPECIALTY ITEMS