

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
<del>20200600</del>	<del>EXCAVATING AND GRADING EXISTING SHOULDER</del>	<del>UNIT</del>	<del>300</del>	<del>300</del>	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	202	202	
<del>28000510</del>	<del>INLET FILTERS</del>	<del>EACH</del>	<del>52</del>	<del>52</del>	
<del>35868100</del>	<del>PREPARATION OF BASE</del>	<del>SQ YD</del>	<del>520</del>	<del>520</del>	
<del>40200000</del>	<del>AGGREGATE SURFACE COURSE, TYPE B</del>	<del>TON</del>	<del>30</del>	<del>30</del>	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	109	109	
40600300	AGGREGATE (PRIME COAT)	TON	49	49	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	83	83	
<del>40800825</del>	<del>POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50</del>	<del>TON</del>	<del>5904</del>	<del>5904</del>	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	800	800	▲
<del>40600990</del>	<del>TEMPORARY RAMP</del>	<del>SQ YD</del>	<del>155</del>	<del>155</del>	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1329	1329	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12317	12317	
<del>40800050</del>	<del>INCIDENTAL HOT MIX ASPHALT SURFACING</del>	<del>TON</del>	<del>30</del>	<del>30</del>	
42001300	PROTECTIVE COAT	SQ YD	410	410	
<del>42300200</del>	<del>PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH</del>	<del>SQ YD</del>	<del>991</del>	<del>991</del>	
<del>42300400</del>	<del>PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH</del>	<del>SQ YD</del>	<del>1526</del>	<del>1526</del>	
<del>42400000</del>	<del>DETECTABLE WARNINGS</del>	<del>SQ FT</del>	<del>60</del>	<del>60</del>	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10151	10151	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	138172	138172	
<del>44000190</del>	<del>HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH</del>	<del>SQ YD</del>	<del>392</del>	<del>392</del>	
<del>44000200</del>	<del>DRIVEWAY PAVEMENT REMOVAL</del>	<del>SQ YD</del>	<del>6332</del>	<del>6332</del>	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5933	5933	
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	5200	5200	

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
<del>44001610</del>	<del>SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)</del>	<del>SQ FT</del>	<del>400</del>	<del>400</del>	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2581	2581	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2688	2688	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	664	664	
<del>44300200</del>	<del>STRIP REFLECTIVE CRACK CONTROL TREATMENT</del>	<del>FOOT</del>	<del>119272</del>	<del>119272</del>	
<del>48101200</del>	<del>AGGREGATE SHOULDERS, TYPE B</del>	<del>TON</del>	<del>220</del>	<del>220</del>	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1281	1281	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1730	1730	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6	
60255500	MANHOLES TO BE ADJUSTED	EACH	16	16	
60260100	INLETS TO BE ADJUSTED	EACH	2	2	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	22	22	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	82	82	
<del>64200105</del>	<del>SHOULDER RUMBLE STRIP</del>	<del>FOOT</del>	<del>1200</del>	<del>1200</del>	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102020	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
<del>70106800</del>	<del>CHANGEABLE MESSAGE SIGN</del>	<del>CAL MO</del>	<del>1</del>	<del>1</del>	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	37,172	37,172	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,483	1,483	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113,964	113,964	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5720	5720	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	220	220	

**LONGO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

USER NAME = #USER#	DESIGNED - MJY	REVISOR -
PLOT SCALE = #SCALE#	DRAWN - RJG	REVISOR -
PLOT DATE = #DATE#	CHECKED - MJY	REVISOR -
	DATE - 04/15/2009	REVISOR -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL ROUTE 25

SCALE: NONE SHEET NO. 3 OF 38 SHEETS STA. 9+80 TO STA. 35+42

Rev. 6-3-09

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	(53 & 54) RS-7	KANE	38	3
D-91-523-09			CONTRACT NO. 60667	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		