

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	300	300	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	202	202	
20000510	INLET FILTERS	EACH	52	52	
35000100	PREPARATION OF BASE	SQ YD	520	520	
40200000	AGGREGATE SURFACE COURSE, TYPE B	TON	30	30	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	109	109	
40600300	AGGREGATE (PRIME COAT)	TON	49	49	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	83	83	
40600625	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	5004	5004	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4114	4114	
40600990	TEMPORARY RAMP	SQ YD	155	155	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1329	1329	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12317	12317	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	30	
42001300	PROTECTIVE COAT	SQ YD	410	410	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	991	991	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1526	1526	
42400000	DETECTABLE WARNINGS	SQ FT	60	60	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10151	10151	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	138172	138172	
44000190	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	392	392	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6332	6332	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5933	5933	
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	5200	5200	

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
44001610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	400	400	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2581	2581	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2688	2688	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	664	664	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	118272	118272	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	220	220	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1281	1281	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1730	1730	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6	
60255500	MANHOLES TO BE ADJUSTED	EACH	16	16	
60260100	INLETS TO BE ADJUSTED	EACH	2	2	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	22	22	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	82	82	
64200105	SHOULDER RUMBLE STRIP	FOOT	1200	1200	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70100000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	37,172	37,172	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,483	1,483	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113,964	113,964	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5720	5720	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	220	220	



USER NAME = #USER#
 DESIGNED - MJY
 DRAWN - RJG
 PLOT SCALE = #SCALE#
 CHECKED - MJY
 PLOT DATE = #DATE#
 DATE - 04/15/2009

REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 25

SCALE: NONE SHEET NO. 3 OF 38 SHEETS STA. 9+80 TO STA. 354+42

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	(53 & 54) RS-7	KANE	38	3
D-91-523-09		CONTRACT NO. 60667		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		