

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 100% STATE		CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 100% STATE			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	56	56			
40600300	AGGREGATE (PRIME COAT)	TON	72	72		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9766	9766			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28960	28960			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1214	1214		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	56	56			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	131	131			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1270	1270		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	131	131			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	77	77		X0322256	TEMPORARY INFORMATIONAL SIGNING	SQ FT	155	155			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2912	2912		X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	25	25			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2889	2889		20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	35	35			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	31778	31778		X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50	TON	1303	1303			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	347	347		20201006	GRADING AND SHAPING SHOULDERS	UNIT	130	130			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	4	4									
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	230	230									
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	17	17									
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100									
55039700	STORM SEWERS TO BE CLEANED	FOOT	1300	1300									
60250200	CATCH BASINS TO BE ADJUSTED	EACH	25	25									
60255500	MANHOLES TO BE ADJUSTED	EACH	25	25									
60260100	INLETS TO BE ADJUSTED	EACH	25	25									
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	65	65									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5									
67100100	MOBILIZATION	L SUM	1	1									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	8705	8705									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28960	28960									

*Specialty Items

LONCO, INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

USER NAME - #USER*	DESIGNED - MJY	REVISED -
PLOT SCALE = #SCALE*	DRAWN - RJG & ST	REVISED -
PLOT DATE = #DATE*	CHECKED - MJY	REVISED -
	DATE - 04/15/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
W HOFF ROAD

SCALE: NONE SHEET NO. 3 OF 18 SHEETS STA. 43+00 TO STA. 173+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
297	1-G-RS-1	WILL	18	3
D-91-550-09			CONTRACT NO. 60694	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.