

SUMMARY OF QUANTITIES				URBAN 100% STATE		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				LAKE COUNTY 1000	COOK COUNTY 1000	
20200100	EARTH EXCAVATION	CU YD	20	10	10	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	30	15	15	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	20	10	10	
35800200	AGGREGATE BASE REPAIR	TON	30	15	15	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	5	5	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12	6	6	
40600300	AGGREGATE (PRIME COAT)	TON	60	30	30	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	1	1	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	5	5	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5	0.5	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	250	250	
40600990	TEMPORARY RAMP	SQ YD	720	360	360	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	50	25	25	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	1	1	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1244	622	622	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	14,800	7,400	7,400	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	10	10	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	280	140	140	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	500	250	250	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	180	90	90	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	210	105	105	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	196	98	98	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	90	45	45	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,300	650	650	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	0	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	1	1	

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% STATE		
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				LAKE COUNTY 1000	COOK COUNTY 1000	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	8	7	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	2	1	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	6	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,520	1,260	1,260	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	480	240	240	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,900	10,450	10,450	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,100	1,050	1,050	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	420	210	210	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	750	375	375	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,400	1,700	1,700	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	160	80	80	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,700	6,350	6,350	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	700	350	350	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	100	100	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	300	150	150	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	180	90	90	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	172	86	86	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	700	350	350	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	26	25	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	584	292	292	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	10	10	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5	

FILE NAME = N:\PROJ\3368\3368_15\Design\ProposedPlan\3368_15-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel: 773.775.4009 Fax 773.775.4014

USER NAME = wjancaster	DESIGNED - MBT	REVISED -
	DRAWN - AL	REVISED -
PLOT SCALE = 1:8000' / 1" IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/21/2009	DATE - 4/16/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

LAKE-COOK ROAD /SHERIDAN ROAD
GREEN BAY ROAD TO SHERIDAN ROAD (EAST JUNCTION)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 19 SHEETS STA. TO STA.

F.A.U. RTE. 3726	SECTION (112 & 112X) RS-7	COUNTY LAKE/COOK	TOTAL SHEETS 19	SHEET NO. 3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60H03	

Rev.