


SUMMARY OF QUANTITIES					SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	URBAN		CONSTRUCTION TYPE CODE	CODE NO.	ITEM	UNIT	URBAN		CONSTRUCTION TYPE CODE
			TOTAL QUANTITIES	1000 100% STATE					TOTAL QUANTITIES	1000 100% STATE	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182	
40600300	AGGREGATE (PRIME COAT)	TON	77	77		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41978	41978	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	320	320	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1587	1587		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	96	96	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12081	12081	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2025	2025		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	101	101		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41978	41978	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3027	3027		* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	320	320	
42001300	PROTECTIVE COAT	SQ YD	98	98		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150	150	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	36070	36070		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	583	583		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	329	329	
44000190	PAVEMENT REMOVAL	SQ YD	568	568		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	329	329	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	448	448		* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	257	257	
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	35	35		X0322256	TEMPORARY INFORMATIONAL SIGNING	SQ FT	257	257	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	190	190		XX005656	INLET FILTER CLEANING	EACH	0	0	
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	223	223		XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	568	568	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	56	56		X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	60	60	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	94	94		Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1174	1174		X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD) 1L 4.75, NSD	TON	1502	1502	
60255500	MANHOLES TO BE ADJUSTED	EACH	30	30							
60260100	INLETS TO BE ADJUSTED	EACH	11	11							
60250200	CATCH BASINS TO BE ADJUSTED	EACH	30	30							
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6							
67100100	MOBILIZATION	L SUM	1	1							
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	12,722	12,722							

*Specialty Items



USER NAME = *USER*	DESIGNED - MJY	REVISOR -
PLOT SCALE = *SCALE*	DRAWN - RJG	REVISIONS -
PLOT DATE = *DATE*	CHECKED - MJY	DATE - 04/15/2009

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
183RD STREET

SCALE: NONE SHEET NO. 3 OF 23 SHEETS STA. 21+50 TO STA. 160+00

OR RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1622	3075 RS-1	COOK	23	3
D-91-575-09		CONTRACT NO. 60H19		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		