

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE		CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	1000 100% STATE	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	212	212		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	111	111		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	30	30		70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	61	61		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5284	5284		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1685	1685		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14033	14033		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
42001300	PROTECTIVE COAT	SQ YD	1381	1381		<del>70106800</del>	<del>CHANGEABLE MESSAGE SIGN</del>	<del>CAL MO</del>	<del>1</del>	<del>1</del>	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8675	8675		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5900	5900	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	145261	145261		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1642	1642	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	82341	82341	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	7520	7520		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3267	3267	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3327	3327		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	452	452	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	3361	3361		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4320	4320	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	832	832		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1683	1683	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	692	692		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	38709	38709	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1240	1240		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1642	1642	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	82341	82341	
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12		* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3267	3267	
60260100	INLETS TO BE ADJUSTED	EACH	14	14		* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	452	452	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	18	18		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4320	4320	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	71	71		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1683	1683	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1581	1581	
67100100	MOBILIZATION	L SUM	1	1		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1581	1581	

\* Specialty Items

Rev.