F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	31	3
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (1919.15 & 2021-922 PT1) I 62985

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN QUANTITY	100% STATE URBAN ROADWAY SFTY-4A
20200100	EARTH EXCAVATION	CU YD	232	232
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	111	111
25000210	SEEDING, CLASS 2A	ACRE	0.03	0.03
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3
25100630	EROSION CONTROL BLANKET	SQ YD	111	111
28000510	INLET FILTERS	EACH	29	29
42001300	PROTECTIVE COAT	SQ YD	215	215
44000600	SIDEWALK REMOVAL	SQ FT	51	51
50300225	CONCRETE STRUCTURES	CU YD	31.9	31.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22.3	22.3
50300300	PROTECTIVE COAT	SQ YD	250	250
50300510	RUSTICATION FINISH	SQ FT	291	291
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,258	4,258
60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	367	367
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	994	994
66410300	CHAIN LINK FENCE REMOVAL	FOOT	1,047	1047
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8
* ~~81000800~~	~~CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL~~	~~FOOT~~	~~10~~	~~10~~
* ~~81200120~~	~~CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL~~	~~FOOT~~	~~5~~	~~5~~
* ~~81900200~~	~~TRENCH AND BACKFILL FOR ELECTRICAL WORK~~	~~FOOT~~	~~10~~	~~10~~
* ~~89502300~~	~~REMOVE ELECTRIC CABLE FROM CONDUIT~~	~~FOOT~~	~~250~~	~~250~~
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
* ~~X0323363~~	~~ELECTRIC CABLE IN CONDUIT, NO. 12 3/C~~	~~FOOT~~	~~250~~	~~250~~
X0324640	FLUTED KNEEWALL	FOOT	915	915
X0324700	WALL MOUNTED SIGN SUPPORT FOR TYPE I PANEL (SPECIAL)	EACH	1	1
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	1,568	1,568
X0321472	TEMPORARY CONCRETE BARRIER REMOVE	FOOT	720	720
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1
Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
* ~~X0326312~~	~~TRAFFIC SIGNAL POST, PAINTED STEEL (SPECIAL) (7 FT.)~~	~~EACH~~	~~1~~	~~1~~

* SPECIALTY ITEM

AECOM

REVISIONS NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63RD ST TO 59TH ST (NB AND SB KNEE WALLS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: NJH
DATE: JANUARY 14, 2009 CHECKED BY: RMG

C:\Documents and Settings\mann\Desktop\Dan Ryan P4CHB028 sqq.dgn 1/13/2009 1:55:45 PM