F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	*	COOK	22	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (2021-922 PTI & 2122-921 PTI) I-1 62986

SUMMARY OF QUANTITIES

100% STATE

CODE NO.	ITEM	UNIT	QUANTITY	URBAN ROADWAY SFTY-4A
20200100	EARTH EXCAVATION	CU YD	126	126
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	82	82
25000210	SEEDING, CLASS 2A	ACRE	0.02	0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2
25100630	EROSION CONTROL BLANKET	SQ YD	82	82
28000510	INLET FILTERS	EACH	14	14
42001300	PROTECTIVE COAT	SQ YD	103	103
44004250	PAVED SHOULDER REMOVAL	SQ YD	354	354
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	722	722
66410300	CHAIN LINK FENCE REMOVAL	FOOT	643	643
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0324640	FLUTED KNEEWALL	FOOT	718	718
X0324700	WALL MOUNTED SIGN SUPPORT FOR TYPE I PANEL (SPECIAL)	EACH	2	2
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	922	922
X0321947a	TEMPORARY CONCRETE BARRIER REMOVE	FOOT	643	643
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1
Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1	1

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59TH ST TO 47TH ST (NORTHBOUND KNEE WALLS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: PHP
DATE: JANUARY 14, 2009 CHECKED BY: NJH

C:\Documents and Settings\mmnn\Desktop\Dan Ryan P40466\29 sqqdgn
1/13/2009 1:55:53 PM