

ROADWAY\*\*  
 TRAFFIC SIGNALS\*\*  
 RAILROAD BRIDGE\*\*  
 CULVERTS\*\*  
 WEST SIDE BULEVARD  
 McLENNAN RD WALL  
 SN 045-2038  
 EAST SIDE BULEVARD  
 McLENNAN RD WALL  
 SN 045-2039\*\*  
 LANDSCAPING\*\*

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES								
				J00-2A	Y031-1F	X631-2B	Y007	Y007	Y007	Y003		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	58	58								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18								
20100500	TREE REMOVAL, ACRES	ACRE	3.25	3.25								
20101700	SUPPLEMENTAL WATERING	UNIT	4.2	4.2								
20200100	EARTH EXCAVATION	CU YD	96,749	96,749								
20200200	ROCK EXCAVATION	CU YD	3,443	3,299				144				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7,510	7,510								
20300100	CHANNEL EXCAVATION	CU YD	2,566	2566								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	255				255					
20800150	TRENCH BACKFILL	CU YD	2,870	2870								
△ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	39,400	39,400								
△ 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	835	835								
△ 25000210	SEEDING, CLASS 2A	ACRE	2.51	2.51								
△ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11								
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	11								
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11								
△ 25200110	SODDING, SALT TOLERANT	SQ YD	835	835								
• 28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	631	631								
△ • 28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	7.00	7.00								
28000300	TEMPORARY DITCH CHECKS	EACH	33	33								
28100105	STONE RIPRAP, CLASS A3	SQ YD	483	483								
28100107	STONE RIPRAP, CLASS A4	SQ YD	111	111								
28100109	STONE RIPRAP, CLASS A5	SQ YD	669	669								
• 28101500	STONE RIPRAP, SPECIAL	SQ YD	22	22								
28200200	FILTER FABRIC	SQ YD	1,285	1285								
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2,421	2,421								
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	397	397								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5								
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	258	258								
40600895	CONSTRUCTION TEST STRIP	EACH	2	2								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	31	31								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	276	276								
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	387	387								
40701976	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4"	SQ YD	1,193	1,193								
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	16,434	16,434								
42001300	PROTECTIVE COAT	SQ YD	19,430	19,430								
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	205	205								
44000100	PAVEMENT REMOVAL	SQ YD	6,912	6,912								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,072	2,072								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,460	2,460								
44000600	SIDEWALK REMOVAL	SQ FT	126	126								
• 44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	4,260	4,260								

• SPECIAL PROVISION  
 •• 80% HPD 20% COUNTY  
 ••• 80% HPP 20% COUNTY  
 △ SPECIALTY ITEMS

FILE NAME =  
 It\Dgn\Civil\Sheet\sq001.dgn

USER NAME = tthornton  
 PLOT SCALE = 1:1  
 PLOT DATE = 4/30/2009

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE - 3/27/09

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**KANE COUNTY  
 DIVISION OF TRANSPORTATION**

**NEW STEARNS ROAD - STAGE 2  
 SUMMARY OF QUANTITIES**  
 SCALE: NONE SHEET NO. 1 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-10-BR	KANE	219	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63073	