

ROADWAY\*\*  
 TRAFFIC SIGNALS\*\*  
 RAILROAD BRIDGE\*\*  
 CULVERTS\*\*  
 WEST SIDE  
 MOLENTON BOULEVARD  
 S/N 045-2038  
 EAST SIDE  
 MOLENTON BOULEVARD  
 S/N 045-2039\*\*  
 LANDSCAPING\*\*

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES										
				J00-2A	Y031-1F	X631	Y007	Y007	Y007	Y007	Y003			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	45	45										
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6,588	6588										
• 60618310	CONCRETE MEDIAN SURFACE, 4 INCH (SPECIAL)	SQ FT	5,181	5,181										
• 60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	1,713	1,713										
△ 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	450	450										
△ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2										
• 63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	629	629										
67100100	MOBILIZATION	L SUM	1	1										
• 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1										
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18										
70300100	SHORT TERM PAVEMENT MARKING	FOOT	400	400										
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	809	809										
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,173	3,173										
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,012.5	1,012.5										
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	887.5	887.5										
72000100	SIGN PANEL - TYPE 1	SQ FT	96.25	70.25	26									
72900200	METAL POST - TYPE B	FOOT	174	174										
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110										
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,772	7,772										
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	694	694										
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	551	551										
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	77	77										
△ • 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	656	656										
△ • 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,436	1,436										
△ • 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2,922	2,922										
△ • 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	105	105										
△ • 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,233	1,233										
△ • 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	250	250										
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	168	168										
△ 78200405	GUARDRAIL MARKERS	EACH	6	6										
△ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4										
△ 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1,936		1936									
△ 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	263		263									
△ 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	109		109									
△ 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	17		17									
△ 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	742		742									
△ 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10		10									
△ 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	77		77									
△ 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	213		213									
△ 81400100	HANDHOLE	EACH	8		8									
△ 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4									
△ 81400300	DOUBLE HANDHOLE	EACH	3		3									

• SPECIAL PROVISION  
 •• 80% HPD 20% COUNTY △ SPECIALTY ITEMS  
 ••• 80% HPP 20% COUNTY

FILE NAME = I:\Dgn\Civil\Sheet\sq004.dgn	USER NAME = tthornton	DESIGNED -	REVISED -	<b>KANE COUNTY DIVISION OF TRANSPORTATION</b>	<b>NEW STEARNS ROAD - STAGE 2 SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 361	SECTION 06-00214-10-BR	COUNTY KANE	TOTAL SHEETS 219	SHEET NO. 7
PLOT SCALE = 1:1	CHECKED -	REVISED -	SCALE: NONE		SHEET NO. 1 OF 7 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 4/30/2009	DATE = 3/27/09	REVISED -	CONTRACT NO. 63073									