

ROADWAY\*\*  
 TRAFFIC SIGNALS\*\*  
 RAILROAD BRIDGE\*\*  
 CULVERTS\*\*  
 WEST SIDE  
 McLEANS BOULEVARD  
 S/N 045-2038  
 EAST SIDE  
 McLEANS BOULEVARD  
 S/N 045-2039\*\*  
 LANDSCAPING\*\*

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES						
				J00-2A	Y031-1F	X631	Y007	Y007	Y007	Y003
• X0321809	PERMANENT GROUND ANCHOR	EACH	95					35	60	
• X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	150	150						
• X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	948		948					
• X0323260	SEDIMENT BASIN	EACH	1	1						
• X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	4	4						
• X0323670	PREFORMED DETECTOR LOOP	FOOT	245		245					
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	7,595	7,595						
• X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	7,595	7,595						
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	1	1						
• X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	5,617					2,404	3213	
• X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	70					50	20	
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	150	150						
• X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	150	150						
• X0325096	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1		1					
• X0325346	RAILROAD TRACK	TR FT	2,395	2,395						
• X0325355	RAILROAD TRACK, REMOVE	TR FT	2,395	2,395						
• X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7,333	7,333						
• X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	476	476						
• X0712400	TEMPORARY PAVEMENT	SQ YD	1,421	1,421						
• X2510635	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL (P550)	SQ YD	2,361	2361						
• X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1						
• X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2		2					
• X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1					
• X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	974		974					
• X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,475		1475					
• X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,159		2159					
• XX003503	FLARED END SECTION REMOVAL	EACH	2	2						
• XX004848	STONE DRIVEWAY REPLACEMENT	SQ YD	80	80						
• XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	EACH	1	1						
• XX005723	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	EACH	1		1					
• XX006128	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL )	EACH	2	2						
• XX006338	EROSION CONTROL BLANKET SPECIAL (S150BN)	SQ YD	1,333	1333						
• XX006628	FILTER FABRIC - INLET PROTECTION	EACH	21	21						
• XX006698	TREE PROTECTION AND PRESERVATION	EACH	3	3						
• XX006701	SEEDING, CLASS 4 (MODIFIED) MESIC PRAIRIE	ACRE	4.33							4.33
• XX006702	SEEDING, CLASS 4 (MODIFIED) WET TO MESIC PRAIRIE	ACRE	0.79							0.79
• XX006706	SEEDING, CLASS 4 (MODIFIED) DETENTION BASIN	ACRE	0.30							0.30
• XX006709	SEEDING, CLASS 5 (MODIFIED) MESIC PRAIRIE	ACRE	4.33							4.33
• XX006710	SEEDING, CLASS 5 (MODIFIED) WET TO MESIC PRAIRIE	ACRE	0.79							0.79
• Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	20,835	20,835						
• Z0002300	BALLAST	CU YD	1,400	1,400						
• Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1						

• SPECIAL PROVISION  
 •• 80% HPD 20% COUNTY  
 ••• 80% HPP 20% COUNTY

FILE NAME = I:\Dgn\Civil\Sheet\sq086.dgn	USER NAME = tthornton	DESIGNED -	REVISED -	<b>KANE COUNTY DIVISION OF TRANSPORTATION</b>	<b>NEW STEARNS ROAD - STAGE 2 SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 361	SECTION 06-00214-10-BR	COUNTY KANE	TOTAL SHEETS 219	SHEET NO. 9
PLOT SCALE = 1:1	CHECKED -	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 7 SHEETS	STA. TO STA.	CONTRACT NO. 63073				
PLOT DATE = 4/30/2009	DATE = 3/27/09	REVISED -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							