



**RESTORATION OF WORK AREA.** RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD. AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

- NOTES:**
1. ALL CALLING DETECTION ZONES ARE APPROXIMATE. THE EXACT LOCATIONS SHALL BE DETERMINED AND LAID OUT IN THE FIELD BY THE MANUFACTURER'S TECHNICIAN AS APPROVED BY THE ENGINEER.
  2. NO LUMINAIRE WILL BE INSTALLED ON THE LUMINAIRE MAST ARMS. THE LUMINAIRE MAST ARMS WILL BE USED EXCLUSIVELY FOR MOUNTING THE VIDEO DETECTION CAMERAS. THE OPEN END OF THE LUMINAIRE MAST ARM SHALL BE COVERED WITH A CAP OF THE SAME MATERIAL AS THE MAST ARM AND A WATER-TIGHT GASKET. THIS MATERIAL AND WORK SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT COST BID FOR "STEEL COMBINATION MAST ARM ASSEMBLY AND POLE" OF THE LENGTH SPECIFIED.
  3. STREET SIGN NAME SIGNS AND "LEFT TURN ON GREEN ARROW ONLY" SIGNS TO BE PROVIDED AND INSTALLED BY KANE COUNTY DEPARTMENT OF TRANSPORTATION.

MATCH LINE A-A (SEE SHEET 2 OF 2)

MATCH LINE B-B (SEE SHEET 2 OF 2)

MATCH LINE C-C (SEE SHEET 2 OF 2)

**STEARNS RD.**

**MCCLEAN BLVD.**

PROPOSED	EXISTING

FILE NAME = I:\Dgn\Civil\Sheet\td005.dgn	USER NAME = sthornton	DESIGNED - MJT	REVISED -	<b>KANE COUNTY DIVISION OF TRANSPORTATION</b>	<b>NEW STEARNS ROAD - STAGE 2 TRAFFIC SIGNAL PLAN - STEARNS RDMCCLEAN BLVD</b>	F.A.P. R.T.E. 361	SECTION 06-00214-10-BR	COUNTY KANE	TOTAL SHEETS 219	SHEET NO. 71
PLOT SCALE = 1:20	CHECKED - TMT	REVISOR -	CONTRACT NO. 63073							
PLOT DATE = 3/27/2009	DATE - 3/27/09	REVISOR -								