

**SCHEDULE OF QUANTITIES**

**DRIVEWAYS**

DRIVEWAYS	EXIST DRIVEWAY APRON (TYPE)	PRIV. OR COMM.	DRIVEWAY PAVEMENT AREA (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	HMA SURF. REM. BUTT JOINT (SQ YD)	LVL. BIN. (MAC. MTH.), N50, 1"	HMA SURF. CRSE, MIX 'C' N50, 1 1/2"	HMA SURF. CRSE, MIX 'C' N50, 2"	HMA BASE CRSE 6"	HMA BASE CRSE 8"	PCC DW. PVT. 8"	SIDEWALK REMOVAL (SQ FT)
LINCOLN AVENUE												
11+35 LT	HMA	CE	23	-	23	-	-	4	-	-	-	-
11+70 LT	HMA	CE	25	-	25	-	-	4	-	-	-	-
12+24 LT	HMA	CE	32	-	32	-	-	5	-	-	-	-
12+64 LT	HMA	CE	11	11	-	-	-	2	-	11	-	72
13+19 LT	PCC/HMA	CE	27	27	-	-	-	2	-	15	12	108
13+45 LT	PCC/HMA	CE	17	17	-	-	-	2	-	10	7	99
15+49 LT	HMA	PE	18	18	-	-	-	3	18	-	-	135
18+50 LT	HMA	PE	20	-	20	2	3	-	-	-	-	-
19+25 LT	HMA	PE	19	-	19	2	3	-	-	-	-	-
19+60 LT	HMA	PE	16	-	16	1	2	-	-	-	-	-
11+84.5 RT (BEACH WAY STATIONING)	HMA	CE	45	-	45	3	5	-	-	-	-	-
100+01 RT	PCC	CE	12	12	-	-	-	-	-	-	12	63
100+15 RT	HMA	CE	13	13	-	-	-	-	-	-	13	45
100+61 RT	PCC	CE	30	30	-	-	-	-	-	-	30	90
15+93 RT (LINCOLN AVENUE (EAST) STATIONING)	GRVL	PE	12	-	12	1	2	-	-	-	-	-
400+75 LT	HMA	PE	16	-	16	1	2	-	-	-	-	-
<b>TOTALS</b>			<b>336</b>	<b>128</b>	<b>208</b>	<b>10</b>	<b>17</b>	<b>22</b>	<b>18</b>	<b>36</b>	<b>74</b>	<b>612</b>

DRIVEWAYS	PCC SIDEWALK 6"	PCC SIDEWALK 8"	AGGREGATE BASE COURSE TYPE B - 4"	AGGREGATE BASE COURSE TYPE B - 6"	COMB. CONCRETE CURB & GUTTER REMOVAL REPLACE.	CURB REMOVAL	CONCRETE CURB, TYPE B	CONCRETE CURB, TYPE B (SPECIAL)
	(SQ FT)	(SQ FT)	(SQ YD)	(SQ YD)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
LINCOLN AVENUE								
11+35 LT	-	-	10	-	42	-	-	-
11+70 LT	-	-	11	-	46	-	-	-
12+24 LT	-	-	12	-	51	-	-	-
12+64 LT	-	72	19	8	34	-	-	-
13+19 LT	-	108	21	24	22	-	-	-
13+45 LT	-	99	13	18	-	12	12	-
15+49 LT	135	-	41	-	-	16	16	16
18+50 LT	-	-	-	-	-	-	-	-
19+25 LT	-	-	-	-	-	-	-	-
19+60 LT	-	-	-	-	-	-	-	-
11+84.5 RT (BEACH WAY STATIONING)	-	-	-	-	-	-	-	-
100+01 RT	-	63	-	19	-	-	-	-
100+15 RT	-	45	-	18	-	-	-	-
100+61 RT	-	90	-	40	-	-	-	-
15+93 RT (LINCOLN AVENUE (EAST) STATIONING)	-	-	-	-	-	-	-	-
400+75 LT	-	-	-	-	-	-	-	-
<b>TOTALS</b>	<b>135</b>	<b>477</b>	<b>127</b>	<b>127</b>	<b>195</b>	<b>28</b>	<b>28</b>	<b>16</b>

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC. ...  
 ILLINOIS PROFESSIONAL ENGINEERING LICENSE NO. 020-000000  
 SURVEYING LICENSE NO. 020-000000  
 3/10/2009 4:39:56 PM



DESIGNED - REW	REVISED - IDOT REVIEW 02-09-09
DRAWN - CJC	REVISED - IDOT REVIEW 03-04-09
CHECKED - RWL	REVISED -
DATE - 12-12-08	FILE - 080923-SCHEDULE.shp

**VILLAGE OF FOX RIVER GROVE, ILLINOIS  
LINCOLN AVENUE STP (LAPP)  
IMPROVEMENTS**

<b>SCHEDULE OF QUANTITIES</b>	
SCALE: NONE	STA. TO STA.

F.A.J. RTE. 0015	SECTION 08-00020-00-RS	COUNTY McHENRY	TOTAL SHEETS 26	SHEET NO. 7
FED. ROAD DIST. NO. C-91-201-09		CONTRACT NO. 63162		
ILLINOIS FED. AID PROJECT M-9003 (167)				