

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00069-00-BT	COOK	24	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS		

ITEM NO.	DESCRIPTION	UNIT	YO47 QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	18
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	38
20200100	EARTH EXCAVATION	CU YD	2140
21101615	TOPSOIL, FURNISH AND PLACE 4"	SQ YD	3900
25000115	SEEDING, CLASS 1B	ACRE	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	100
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	100
25200200	SUPPLEMENTAL WATERING	UNIT	30
28000400	PERIMETER EROSION BARRIER	FOOT	4007
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	2120
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	5880
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	520
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2120
42400800	DETECTABLE WARNINGS	SQ FT	40
44000600	SIDEWALK REMOVAL	SQ FT	850
44001700	COMBINATION CONCRETE CURB & GUTTER REMOVAL & REPLACEMENT	FOOT	8
50900805	PEDESTRIAN RAILING	FOOT	96
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	18
54213655	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 10"	EACH	4
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	2
542A0215	PIPE CULVERTS, CLASS A, TYPE 1 10"	FOOT	48
60608300	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.12	FOOT	20
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	130
66400205	CHAIN LINK FENCE, 5'	FOOT	610
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	100
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5
72900100	METAL POST - TYPE A	FOOT	150
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4007
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	270
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	6


\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE
IDOT REVIEW	3-3-09
IDOT REVIEW	3-17-09

SUMMARY OF QUANTITIES  
PEDESTRIAN / BIKE TRAIL  
HAZEL CREST, IL  
SECTION NO. 06-00069-00-BT

SCALE: VERT. N/A  
HORIZ. N/A  
DATE 01/14/09  
DRAWN BY L.S.  
CHECKED BY D.W.S.

CIVIL / STRUCTURAL ENGINEERS



GLOBETROTTERS INTERNATIONAL,  
300 SOUTH WACKER DRIVE, SUITE 200  
CHICAGO, IL. 60606

P:\oad\msv8\pen\_tables\dot.tbl Color - Monochrome  
tds600-raster on fs0.plt