

PAY ITEM #	ITEM	UNIT	TOTAL QUANTITY	I 000 - 2A QUANTITY
20100210	TREE REMOVAL (OVER 15 UNITS DIA)	UNITS	146	146
20200500	EARTH EXCAVATION (WIDENING)	CY	1308	1308
20700220	POROUS GRANULAR EMBANKMENT	CY	100	100
20800150	TRENCH BACKFILL	CY	640	640
21101615	TOPSOIL FURNISH AND PLACE, 4"	SY	5150	5150
25200110	SODDING, SALT TOLERANT	SY	5150	5150
25200200	SUPPLEMENTAL WATERING	UNIT	50	50
28000400	PERIMETER EROSION BARRIER	FOOT	3794	3794
28000510	INLET FILTERS	EA	35	35
35102000	AGGREGATE BASE COURSE TYPE B - 8"	SY	180	180
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING - 8"	SY	2940	2940
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	720	720
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	120	120
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19, N50	TON	1114	1114
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	780	780
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SF	6650	6650
42400800	DETECTABLE WARNINGS	SF	500	500
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SY	6680	6680
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4610	4610
44000600	SIDEWALK REMOVAL	SF	6650	6650
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	990	990
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	25	25
55020000	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 27"	FOOT	20	20
55100300	STORM SEWER REMOVAL, 8"	FOOT	750	750
* 56400500	FIRE HYDRANT TO BE REMOVED	EA	2	2
* 56400820	FIRE HYDRANT WITH AUXILARY VALVE AND VALVE BOX	EA	2	2
60218400	MANHOLES, TYPE A, 4' DIAMETER TYPE 1 FRAME, CLOSED LID	EA	3	3
60221100	MANHOLES, TYPE A, 5' DIAMETER TYPE 1 FRAME, CLOSED LID	EA	1	1
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EA	35	35
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EA	22	22
60500050	REMOVING CATCHBASINS	EA	35	35
60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	FOOT	4610	4610
67100100	MOBILIZATION	LS	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LS	1	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4080	4080
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600
X0322924	RETAINING WALL REMOVAL	SF	180	180
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SY	1380	1380
XX001910	PRECAST BLOCK RETAINING WALL	SF	180	180
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SY	1510	1510
△ Z0076600	TRAINEES	HOUR	500	500

△ Y080 * SPECIALTY ITEMS