

BRF

← NHF →

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	50% STATE 50% CITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	75% STATE 25% CITY	100% CITY
				X071-2A TOTAL QUANTITY	X071-2A TOTAL QUANTITY	SFTY-2A TOTAL QUANTITY	J000 TOTAL QUANTITY	Y044 TOTAL QUANTITY	Y044 TOTAL QUANTITY	SFTY-2A TOTAL QUANTITY
44213200	SAW CUTS	FOOT	1135					1135		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1					1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1					1		
50105220	PIPE CULVERT REMOVAL	FOOT	84							
50200100	STRUCTURE EXCAVATION	CU YD	192	192						
50300225	CONCRETE STRUCTURES	CU YD	188	188						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218.4	192.4	26					
50300260	BRIDGE DECK GROOVING	SQ YD	420	420						
50300280	CONCRETE ENCASEMENT	CU YD	11	11						
50300300	PROTECTIVE COAT	SQ YD	785	785						
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	629			629				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1						
50500505	STUD SHEAR CONNECTORS	EACH	2520	2520						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	69380	61340	8040					
50800515	BAR SPLICERS	EACH	691	691						
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	216			216				
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1080.4	1080.4						
51202305	DRIVING PILES	FOOT	1080.4	1080.4						
51203600	TEST PILE STEEL HP12X53	EACH	2	2						
51204650	PILE SHOES	EACH	32	32						
51205200	TEMPORARY SHEET PILING	SQ FT	103	103						
51500100	NAME PLATES	EACH	1	1						
52100520	ANCHOR BOLTS, 1"	EACH	56	56						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2				2			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1				1			
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1				1			
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	25				25			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	862				862			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	98				98			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	66				66			
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	145				145			
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	381				381			
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	12				12			
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	57				57			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	30				30			
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	31				31			
550A2610	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 42"	FOOT	104				104			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1							1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	82			82				

* SPECIALTY ITEMS

FILE NAME =	USER NAME = jordanhd	DESIGNED -	REVISED -
ca\p\work\PWIDOT\JORDANHD\dms34552\sl1325\cvr.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Mon Mar 16 08:07:17 2009		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	(17)B	WHITESIDE	376	4
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64B74	