

70301000	WORK ZONE PAVEMENT MARKING REMOVAL			
	LOCATION	SQ. FT		REMARKS
	PRE-STAGE 2			
	STA 1034+26.00 TO 1041+77.96	501.31		DOUBLE YELLOW EXISTING PAVEMENT STRIPING
	PRE-STAGE 3			
	STA 1035+12.90 TO 1041+04.97	197.36		
	PRE-STAGE 3A			
	STA 1034+27.62	24.00		24" STOP BAR
	STA 1034+37.55 TO 1041+00.80	221.08		
	STA 1041+75.80	25.00		24" STOP BAR
	PRE-STAGE 4			
	STA 1044+33.29 TO 1047+38.56	203.51		DOUBLE YELLOW EXISTING PAVEMENT STRIPING
	PRE-STAGE 5			
	STA 1039+56.78 TO 1046+76.72	241.29		
	PRE-STAGE 5A			
	STA 1039+46.78	27.00		24" STOP BAR
	STA 1040+06.78 TO 1045+26.74	190.21		
	STA 1047+36.56	26.00		24" STOP BAR
	STAGE 1			
	STA 1032+38.56 TO 1034+22.69	61.38		
	STA 1040+64.76 TO 1042+62.22	65.82		
	STAGE 2			
	STA 1027+62.75 TO 1029+91.78	152.69		DOUBLE YELLOW EXISTING PAVEMENT STRIPING
	STA 1029+08.39 TO 1030+92.74	61.45		
	STA 1040+23.95 TO 1048+06.80	260.95		
	STA 1040+34.56 TO 1042+62.34	151.85		DOUBLE YELLOW EXISTING PAVEMENT STRIPING
	STA 1042+64.22	26.00		24" STOP BAR
	STAGE 2A			
	STA 1027+61.90 TO 1031+30.05	122.72		
	STA 1027+62.75	24.00		24" STOP BAR
	STA 1029+21.55 TO 1031+30.05	69.50		
	STA 1042+62.24	42.00		24" STOP BAR
	STAGE 3			
	STA 1036+87.27 TO 1038+82.27	65.00		
	STA 1036+87.27 TO 1048+06.80	373.18		
	STA 1047+63.03 TO 1050+29.09	177.37		DOUBLE YELLOW EXISTING PAVEMENT STRIPING
	STAGE 3A			
	STA 1035+77.49	24.00		24" STOP BAR
	STA 1035+87.49 TO 1038+82.27	98.26		
	STA 1036+87.27 TO 1038+82.27	65.00		
	STA 1046+62.00 TO 1049+69.09	102.36		
	STA 1050+29.09	24.00		24" STOP BAR
	TOTAL	= 3624.29		

70400100	TEMPORARY CONCRETE BARRIER			
	LOCATION	FOOT		REMARKS
	STA 1036+37 TO 1039+36	300	RT	PRESTAGE 2
	STA 1036+00 TO 1039+74	75		PRESTAGE 3
	STA 1040+74 TO 1044+97	50	RT/LT	PRESTAGE 4
	STA 1034+63 TO 1040+25	350	LT	STAGE 1
	STA 1029+31 TO 1040+69	787.00	RT / LT	STAGE 2
	STA 1036+69 TO 1038+94	12.50	LT	STAGE 2
	TOTAL	= 1574.50		

70400200	RELOCATE TEMPORARY CONCRETE BARRIER			
	LOCATION	FOOT		REMARKS
	PRE-STAGE 3			
	STA 1036+00 TO 1039+74	300	RT	FROM PRE-STAGE 2
	PRE-STAGE 4			
	STA 1040+74 TO 1044+97	375	RT / LT	FROM PRE-STAGE 3
	PRE-STAGE 5			
	STA 1041+34 TO 1043+47	212.50	LT	FROM PRE-STAGE 4
	STAGE 1			
	STA 1034+63 TO 1040+25	212.50	LT	FROM PRESTAGE 5
	STAGE 2			
	STA 1036+69 TO 1038+94	212.50	LT	FROM STAGE 1
	STA 1029+31 TO 1040+69	350.00	RT / LT	FROM STAGE 1
	STAGE 3			
	STA 1037+25 TO 1038+87	50	LT	112.5 LF REMAINS IN PLACE FROM STAGE 2
	STA 1037+63 TO 1048+25	1062.00	RT / LT	FROM STAGE 2
	TOTAL	= 2774.50		

78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"			
	LOCATION	FOOT		REMARKS
	STA 1031+14.42 TO STA 1046+71.91	3114.98		DOUBLE YELLOW
	MILNES DRIVE	83.91		DOUBLE YELLOW
	YELLOW TOTAL	= 3198.89		

	LOCATION	FOOT		REMARKS
	STA 1031+29.90 TO STA 1044+01.55	1271.15	LT	
	STA 1031+30.09 TO STA 1046+62.00	1524.22	RT	
	STA 1045+36.89 TO STA 1046+62.00	113.11	LT	
	WHITE TOTAL	= 2908.48		
	OVERALL TOTAL	= 6107.37		

78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"			
	LOCATION	FOOT		REMARKS
	STA 1044+31.06 TO STA 1044+99.59	68.53	26' LT	CROSS WALK
	STA 1044+38.83 TO STA 1044+87.80	48.97	38.5' LT	DOUBLE YELLOW
	TOTAL	= 117.50		

78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"			
	LOCATION	FOOT		REMARKS
	MILNES DRIVE	18.00		
	TOTAL	= 18.00		

78100100	RAISED REFLECTIVE PAVEMENT MARKER			
	LOCATION	EACH		REMARKS
	STA 1031+14.44 TO STA 1046+71.91	28		
	YELLOW TOTAL	= 28		

Z0007601	BUILDING REMOVAL NO. 1			
	LOCATION	L SUM		REMARKS
	STA 1036+50.00	1	LT	HOUSE (NON-FRIABLE ASBESTOS)
	TOTAL	= 1		

Z0007602	BUILDING REMOVAL NO. 2			
	LOCATION	L SUM		REMARKS
	STA 1036+50.00	1	LT	GARAGE (NO ASBESTOS)
	TOTAL	= 1		

Z0023800	FILL EXISTING SEPTIC TANK			
	LOCATION	EACH		REMARKS
	STA 1036+50.00	1	LT	
	TOTAL	= 1		

Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS			
	LOCATION	EACH		REMARKS
	STA. 1035+91.84	1	RT	42.62'
	STA. 1035+97.88	1	RT	70.00'
	STA. 1036+10.37	1	RT	85.00'
	STA. 1036+20.79	1	RT	90.00'
	STA. 1036+56.11	1	RT	95.00'
	STA. 1036+66.09	1	RT	116.56'
	STA. 1036+86.04	1	RT	115.35'
	STA. 1036+80.83	1	RT	42.56'
	TOTAL	= 8		

Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3			
	LOCATION	EACH		REMARKS
	4 QUADRANTS OF BRIDGE	4		REACT 350 QUADGUARD (FULLY-REDIRECTIVE, NARROW) TEST LEVEL III
	TOTAL	= 4		