

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED 10% STATE
				NONE SFTY - 2A RURAL
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	75	75
44000100	PAVEMENT REMOVAL	SQ YD	79	79
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1,066	1,066
44000400	GUTTER REMOVAL	FOOT	834	834
44004250	PAVED SHOULDER REMOVAL	SQ YD	152	152
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	249	249
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,645	1,645
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	48	48
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	1,980	1,980
50100300	REMOVAL OF EXISTING STRUCTURE NO. 1	EACH	1	1
50100400	REMOVAL OF EXISTING STRUCTURE NO. 2	EACH	1	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	129	129
542D5470	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	64	64
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	121	121
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	508	508
54213450	END SECTIONS 15"	EACH	4	4
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
54214290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	2	2
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	4	4
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	16	16
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	6	6
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4
* 56400200	FIRE HYDRANTS TO BE MOVED (SPECIAL)	EACH	2	2

* SPECIALTY ITEMS
:) NON PARTICIPATING

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
os\pr_work\PWIDOT\DOSSDD\dms41852\d07008cavr.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	553	120M	OGLE	71	4
		CHECKED -	REVISED -						CONTRACT NO. 64E55						
		DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						
PLOT SCALE = 50.0000' / IN.															
PLOT DATE = Tue Jan 13 15:28:23 2009															