

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED
				10% STATE
				NONE
				SFTY - 2A
				RURAL
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,608	1,608
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	55	55
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	179	179
* 72000100	SIGN PANEL, TYPE I	SQ FT	141	141
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	200	200
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,509	9,509
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	612	612
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	734	734
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132	132
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	96	96
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19	19
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
* 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	226	226
* 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	894	894
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	633	633
* 82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	6	6
* 82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1
* 83055300	LIGHT POLE, 45 FT. M.H., TENON MOUNT	EACH	2	2
* 83055310	LIGHT POLE, 45 FT. M.H., TENON MOUNT - TWIN	EACH	2	2
* 83600100	LIGHT POLE FOUNDATION	EACH	4	4
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	16	16

* SPECIALTY ITEMS
 :) NON PARTICIPATING

FILE NAME =	USER NAME = dosedd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr\pw_work\PWIDOT\DDSSDD\dms41852\d07080vrr.dgn		DRAWN -	REVISED -						553	120M	OGLE	71	6
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 64E55				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = Tue Feb 10 10:56:44 2009		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			