

**TABULATION OF LIGHTING AND FLASHING BEACON SYSTEM**

| PAY CODE   | ITEM   | UNIT  | TOTAL |
|------------|--|-------|-------|
| *          | WIRELESS VEHICLE DETECTION AND WARNING SYSTEM COMPLETE                         | EACH  | 1     |
| 72000100   | SIGN PANEL, TYPE I   | SQ FT | 141   |
| 80400100   | ELECTRIC SERVICE INSTALLATION  | EACH  | 1     |
| 81020500   | CONDUIT PUSHED 2" DIA., INTERMEDIATE METAL                                     | FOOT  | 226   |
| 81603000   | UNIT DUCT, 600V, 2-1C NO. 8 1/2 NO. 8 GROUND (XLP-TYPE USE), 3/4" POLYETHYLENE | FOOT  | 894   |
| 81900200   | TRENCH AND BACKFILL FOR ELECTRICAL WORK  | FOOT  | 633   |
| 82104000   | LUMINAIRE SODIUM VAPOR, MULTI-MOUNT 400 WATT                                   | EACH  | 6     |
| 82500605   | LIGHTING CONTROLLER PHOTOCELL RELAY  | EACH  | 1     |
| 83034400   | LIGHT POLE, STEEL, 45 FT M.H., TENON MOUNT                                     | EACH  | 2     |
| 83035400   | LIGHT POLE, STEEL, 45 FT M.H., TENON MOUNT - TWIN                              | EACH  | 2     |
| * 83600100 | LIGHT POLE FOUNDATION  | EACH  | 4     |
| 83800650   | BREAKAWAY DEVICE COUPLING, WITH STAINLESS STEEL SCREEN                         | EACH  | 16    |
| 87502450   | TRAFFIC SIGNAL POST, STEEL, 11 FT  | EACH  | 2     |
| 87800100   | CONCRETE FOUNDATION, TYPE A  | FOOT  | 12    |
| 89501150   | RELOCATE EXISTING TRAFFIC SIGNAL POST  | EACH  | 2     |
| 89502380   | REMOVE EXISTING HANDHOLE   | EACH  | 2     |
| * 89502400 | REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE                          | EACH  | 1     |
| * X0323223 | MAINTAIN EXISTING LIGHTING SYSTEM  | L SUM | 1     |
| * X0323319 | POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)                            | EACH  | 6     |
| *          | SOLAR-POWER FLASHING BEACON ASSEMBLY (COMPLETE)                                | EACH  | 4     |
| * X0325541 | REMOVE EXISTING LIGHTING SYSTEM  | L SUM | 1     |