

**PAVEMENT REMOVAL**

SQ YD	LOCATION	OFFSET	REMARKS
256	34+84.4 TO 37+33.8		
80	38+50.8 TO 40+63.5		
<b>336</b>	<b>TOTAL</b>		

**MEDIAN REMOVAL (SPECIAL)**

SQ YD	LOCATION	OFFSET	REMARKS
230	38+86.2 TO 42+05.9		
<b>230</b>	<b>TOTAL</b>		

**PAVEMENT PATCHING, TYPE II, 13 INCHES**

SQ YD	LOCATION	OFFSET	REMARKS
15	36+00.0		STORM SEWER
16	38+54.0		STORM SEWER
<b>31</b>	<b>TOTAL</b>		

**PAVEMENT PATCHING, TYPE IV, 13 INCHES**

SQ YD	LOCATION	OFFSET	REMARKS
131	36+15.7 TO 37+84.4		USED INSTEAD OF SHOULDER REMOVAL
53	38+86.2 TO 42+05.9		REMOVAL PAID FOR AS MEDIAN REM (SPECIAL)
<b>184</b>	<b>TOTAL</b>		

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"**

EACH	LOCATION	OFFSET	REMARKS
1	36+00.0	RT	STORM SEWER OUTLET

**STORM SEWER, CLASS A, TYPE 1, 12"**

FOOT	LOCATION	OFFSET	REMARKS
43	36+00.0		
27	38+54.0		
<b>70</b>	<b>TOTAL</b>		

**INLETS, SPECIAL, NO. 2**

EACH	LOCATION	OFFSET	REMARKS
1	36+00.0		
1	38+54.0		
<b>2</b>	<b>TOTAL</b>		

**CONCRETE MEDIAN SURFACE 6 INCH**

SQ FT	LOCATION	OFFSET	REMARKS
862.6	36+02.4 TO 37+31.2		LEFT TUNLANE MEDIAN
243.7	38+57.2 TO 40+57.0		LANE MEDIAN
586.6	39+34.3 TO 41+89.7		MEDIAN
<b>1692.9</b>	<b>TOTAL</b>		

**CONCRETE MEDIAN SURFACE CORRUGATED**

SQ FT	LOCATION	OFFSET	REMARKS
660	34+84.3 TO 35+94.4		LANE MEDIAN

**SHORT-TERM PAVEMENT MARKING**

FOOT	LOCATION	OFFSET	REMARKS
128	34+50.0 TO 37+50.0	EB &WB	Shoulder
320	34+50.0 TO 43+30.0	WB	Center Line
64	39+98.7 TO 41+63.7	WB	Lt - turnlane
96	40+63.6 TO 43+30.0	EB	Center Line
<b>608</b>	<b>TOTAL</b>		

**WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION	OFFSET	REMARKS
10.7	34+50.0 TO 37+50.0	EB &WB	Shoulder
26.7	34+50.0 TO 43+30.0	WB	Center Line
5.3	39+98.7 TO 41+63.7	WB	Lt - turnlane
8.0	40+63.6 TO 43+30.0	EB	Center Line
166.7	To Be Used with Standard 701422 if needed		Estimated
<b>217.4</b>	<b>TOTAL</b>		

**THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS**

SQ FT	LOCATION	OFFSET	REMARKS
15.6	35+04.6 EB	12.49' LT	LT Turn Arrow
15.6	35+74.4 EB	17.69' LT	LT Turn Arrow
15.6	36+43.8 EB	21.0' LT	LT Turn Arrow
15.6	37+13.8 EB	21.0' LT	LT Turn Arrow
15.6	39+18.7 WB	21.35' RT	LT Turn Arrow
15.6	39+93.7 WB	21.35' RT	LT Turn Arrow
15.6	40+68.7 WB	21.35' RT	LT Turn Arrow
15.6	41+43.7 WB	21.35' RT	LT Turn Arrow
<b>124.8</b>	<b>TOTAL</b>		