

THERMOPLASTIC PAVEMENT MARKING - 4"

FOOT	LOCATION	OFFSET	REMARKS
2307	13+21.9 TO 37+33.8	EB	Double Yellow
213	34+50.0 TO 36+63.0	WB	Yellow Edge
78	34+50.0 TO 37+62.5	WB	White - Skipdash
392	34+50.0 TO N Weldon	WB	White - Edge
392	34+50.0 TO S Weldon	EB	White - Edge
500	36+15.7 TO 37+33.8		Double Yellow
523	N Weldon Rd TO 43+30.0	WB	White - Edge
523	S Weldon Rd TO 43+30.0	EB	White - Edge
111	38+87.0 TO 43+30.0	WB	White - Skipdash
100	38+98.9 TO 39+23.4		Double Yellow
1091	40+63.6 TO 42+36.3	EB	White - Median
23	42+36.3 TO 43+30.0	EB	White - Skipdash
6253	TOTAL		

THERMOPLASTIC PAVEMENT MARKING - 8"

FOOT	LOCATION	OFFSET	REMARKS
56	32+60.0 TO 34+84.3	EB	WHITE-SKIPDASH
125	34+84.3 TO 35+94.4	EB	WHITE-MEDIAN
425	38+50.8 TO 40+63.5	EB	WHITE-MEDIAN
165	38+98.7 TO 41+63.7	WB	WHITE-TURNLANE
35	41+63.7 TO 43+02.7	WB	WHITE-SKIPDASH
806	TOTAL		

THERMOPLASTIC PAVEMENT MARKING - 12"

FOOT	LOCATION	OFFSET	REMARKS
95	13+21.9 TO 17+50.0		YELLOW-DIAGONAL 30'-OC
325	17+50.0 TO 37+33.8		YELLOW-DIAGONAL 15'-OC
90	32+65.0 TO 34+50.0		YELLOW-DIAGONAL 8'-OC
90	36+15.7 TO 37+33.8		WHITE-DIAGONAL 20'-OC
8	38+98.9 TO 39+23.4		YELLOW-DIAGONAL 75'-OC
13	40+63.6 TO 42+36.3		YELLOW-DIAGONAL 30'-OC
621	TOTAL		

THERMOPLASTIC PAVEMENT MARKING - 24"

FOOT	LOCATION	OFFSET	REMARKS
16	N Weldon Rd		STOPBAR
16	S Weldon Rd		STOPBAR
32	TOTAL		

RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	OFFSET	REMARKS
2	34+50.0 TO	EB	Mono-Crystal
24	34+50.0 TO 43+30.0	WB	80' OC - CL Mono-Crystal
7	36+15.7 TO 37+33.8	MEDIAN	40' OC Mono-Crystal
8	38+98.7 TO 41+63.7	WB	Lt-TL 40' OC Mono-Crystal
10	40+63.6 TO 42+36.3	EB	Lane Median 40' OC Mono-Amber
2	42+50.0 TO	EB	Mono-Crystal
53	TOTAL		

PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	OFFSET	REMARKS
136	18+50.0 TO 34+84.3		

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	OFFSET	REMARKS
65	34+50.0 TO 43+30.0		ESTIMATE QUANTITY

GRANULAR SUBGRADE REPLACEMENT

CU YD	LOCATION	OFFSET	REMARKS - TO BE USED IF NEEDED
42.7	34+84.4 TO 37+33.8		MEDIAN & CURB & GUTTER
21.8	36+15.7 TO 37+94.0		PAVEMENT PATCHING
13.3	38+50.8 TO 40+63.5		MEDIAN & CURB & GUTTER
8.8	38+86.2 TO 42+05.9		PAVEMENT PATCHING
29.5	38+86.2 TO 42+05.9		MEDIAN & CURB & GUTTER
116.1	TOTAL		

GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION	OFFSET	REMARKS - TO BE USED IF NEEDED
256.1	34+84.4 TO 37+33.8		MEDIAN & CURB & GUTTER
130.9	36+15.7 TO 37+94.0		PAVEMENT PATCHING
79.9	38+50.8 TO 40+63.5		MEDIAN & CURB & GUTTER
52.7	38+86.2 TO 42+05.9		PAVEMENT PATCHING
176.8	38+86.2 TO 42+05.9		MEDIAN & CURB & GUTTER
696.4	TOTAL		