



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 8, 2009

SUBJECT: FAI Route 39
Section (50-7B)I-2
LaSalle County
Contract No. 66890
Item No. 243, June 12, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: George F. Ryan, Region 2, District 3; Bill Frey; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66890

State Job # - C-93-040-09
 PPS NBR - 0-01616-3001
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - (50-7B)I-2

Project Number

Route

FAI 39

* REVISED : JUNE 4, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0321468	PLUG EX DK DRAINS	EACH	4.000				
X0322194	POLY MOD P C MORTAR	SQ FT	73.000				
X0322489	BR DK LTX C OLY 2 1/2	SQ YD	2,177.000				
X0323491	SLOPE WALL CRACK SEAL	FOOT	67.000				
X0325305	STR REP CON DP = < 5	SQ FT	96.000				
Z0006225	BR DECK HY-SCAR 2 1/2	SQ YD	2,177.000				
Z0016000	DECK SLAB REP (FD)	SQ YD	40.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	2.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	2.000				
Z0032470	JOINT SEALER	FOOT	119.000				
Z0065700	SLOPE WALL REPAIR	SQ YD	15.000				
44000915	HMA SURFACE RM (DECK)	SQ YD	1,200.000				
44000920	BIT CONC SHLD REM	SQ YD	2,232.000				
44200541	CL A PATCH T2 9	SQ YD	100.000				
48203033	HMA SHOULDERS 9	SQ YD	1,120.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66890

State Job # - C-93-040-09
 PPS NBR - 0-01616-3001
 County Name - LASALLE- -
 Code - 99 - -
 District - 3 - -
 Section Number - (50-7B)I-2

Project Number

Route

FAI 39

* REVISED : JUNE 4, 2009

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48300400	PCC SHOULDERS 9	SQ YD	2,232.000				
50102400	CONC REM	CU YD	56.000				
50300225	CONC STRUCT	CU YD	12.000				
50300255	CONC SUP-STR	CU YD	44.000				
50300260	BR DECK GROOVING	SQ YD	1,134.000				
50300300	PROTECTIVE COAT	SQ YD	1,200.000				
50300530	FLOOR DRAIN EXTENSION	EACH	5.000				
50800205	REINF BARS, EPOXY CTD	POUND	10,344.000				
50800515	BAR SPLICERS	EACH	100.000				
52000110	PREF JT STRIP SEAL	FOOT	170.000				
59000200	EPOXY CRACK INJECTION	FOOT	29.000				
67100100	MOBILIZATION	L SUM	1.000				
70101605	TC-PROT 701402 SPL	EACH	2.000				
70400100	TEMP CONC BARRIER	FOOT	800.000				
70400200	REL TEMP CONC BARRIER	FOOT	750.000				

