

CLASS A PATCHING SCHEDULE - NBL

LOCATION BY LOG MILE	PASSING LANE						DRIVING LANE						REMARKS
	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	
	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				
40.3													PROJECT BEGIN, LASALLE/MARSHALL COUNTY LINE (MILE MARKER 40.3)
40.33			27	27	108	10			27	27	108	10	
40.35							8			8	66		
40.36			27	27	108	10							RTE 18
41.30													
47.70	8			8	66		8			8	66		
47.90	8			8	66		8			8	66		
47.95	8			8	66								
48.35													TONICA RTE 71
51.40							8			8	66		RTE 251 OGLESBY
51.80													
52.10													
53.40							8			8	66		
54.20													ABRAHAM LINCOLN BRIDGE
54.50													
56.20	8			8	66		8			8	66		
56.30	13			13	78								
56.40													RTE 6
57.20									27	27	88	10	
58.60													RTE 80 APPROACH PAVEMENT
62.10							8			8	60		APPROACH PAVEMENT
62.20							8			8	60		RAMP
65.40							8			8	60		RTE 52
65.70													
66.90				8	60		13			13	68		
67.00	8			8	68								
67.10	13			13			8			8	60		
71.60													RTE 34 RAMP
71.80							8			8	60		
72.40							8			8	60		
75.70									27	27	88	10	
76.50													PROJECT ENDS, LASALLE/LEE COUNTY LINE
TOTALS	67		53	120	686	20	109		80	189	1108	30	