

CLASS A PATCHING SCHEDULE - SBL

LOCATION BY MILE MARKER	PASSING LANE						DRIVING LANE						REMARKS
	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	CLASS A PATCHING			PATCH REINF. SQ YD	SAW CUTS FOOT	TIE BARS EACH	
TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD	TYPE II SQ YD				TYPE III SQ YD	TYPE IV SQ YD					
76.50													PROJECT BEGIN, LASALLE LEE COUNTY LINE (MILE MARKER 76.5)
76.30								20		20		78	
74.70							8			8		60	
73.90							13			13		68	
72.40									27	27		88	
72.35							13			13		68	
71.60							8			8		60	
71.40							8			8		60	
70.50							8			8		60	
70.00							8			8		60	
69.70							8			8		60	
69.40							8			8		60	
68.20							13			13		68	
68.15							13			13		68	
67.80							13			13		68	
67.00							8			8		60	
66.95	8			8	60								
66.90							8			8		60	
66.70							13			13		68	
66.30							8			8		60	
65.60													RTE 52
64.20							8			8		60	
63.40							8			8		60	
62.90							8			8		60	
62.10							13			13		68	APPROACH PAVEMENT
60.40							8			8		60	
59.80							8			8		60	
59.75							8			8		60	
59.30							8			8		60	
58.60													RTE 80
58.30							8			8		60	
57.20								20		20		78	
56.80								20		20		78	
56.40													RTE 6 ABRAHAM LINCOLN BRIDGE
55.80									20	20		93	
54.20													OGLESBY
53.20													RTE 251
52.20	8			8	66								RTE 71
52.10													
51.30							8			8		66	
51.10							8			8		66	
50.30							8			8		66	
50.10							8			8		66	
48.60													
48.30													TONICA
47.85	8			8	66		8			8		66	APPROACH PAVEMENT
47.50							8			8		66	
44.60	8			8	66								
43.50							8			8		66	
43.00								20		20		93	APPROACH PAVEMENT
42.70	8			8	66								
42.10							13			13		78	
42.00	8			8	66								
41.30													RTE 18
40.30													PROJECT ENDS, LASALLE/MARSHALL COUNTY LINE
TOTALS	48			48	390		298	100	27	425	2544	10	

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED -
ca:\pwork\PWIDOT\WOODSHANKRL\dms91664	D366934-detail.dgn	DRAWN - RON WOODSHANK	REVISED -
	PLOT SCALE = 1/8" = 100'-00" / IN.	CHECKED -	REVISED -
	PLOT DATE = Mar 31, 2009 - 01:24:35 PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES - SBL

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	VARIOUS	LASALLE	14	6
CONTRACT NO. 66934				

ILLINOIS