

SUMMARY OF QUANTITIES

CONSTR. CODE
STARK CO.
100% FEDERAL
ROADWAY
I000
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	98	98
40600300	AGGREGATE (PRIME COAT)	TON	485	485
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	611	611
40600990	TEMPORARY RAMP	SQ YD	240	240
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	20361	20361
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	241587	241587
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	1934	1934
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	274	274
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	497	497
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1343	1343
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1900	1900
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12
63200600	STEEL PLATE BEAM GUARD RAIL REMOVAL, SINGLE RAIL	FOOT	2350	2350
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	10	10
66700605	PERMANENT SURVEY TIES	EACH	40	40
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19726	19726
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	159479	159479

* Denotes Specialty Items