

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
686	*	FULTON	19	2
STA. 198+00		TO STA. 202+25		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D4 CULVERT EXT. 2008				

## GENERAL NOTES

### UTILITIES - LOCATIONS INFORMATION ON PLANS

THE LOCATIONS OF EXISTING WATER MAINS, GAS MAINS, SEWERS, ELECTRICAL POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS SHOWN ON THE PLANS ARE BASED ON CAREFUL FIELD INVESTIGATION AND THE BEST INFORMATION AVAILABLE, BUT THEY ARE NOT GUARANTEED. UNLESS ELEVATIONS ARE SHOWN - ALL UTILITY LOCATIONS SHOWN ON THE CROSS SECTIONS ARE BASED ON THE APPROXIMATE DEPTH SUPPLIED BY THE UTILITY COMPANY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THE EXACT LOCATION FROM THE UTILITY COMPANIES AND BY FIELD INSPECTION.

### CLEARING

AT LOCATIONS WHERE CLEARING IS INDICATED ON THE PLANS BEYOND THE LIMITS OF THE PROPOSED EXCAVATION OR EMBANKMENT, THE CONTRACTOR SHALL RESTORE THE DISTURBED EARTH BY BLADING AND SHAPING TO BLEND WITH ADJACENT GROUND. THE CLEARING WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION. RESEEDING OR RESODDING WILL BE AS PROVIDED IN THE PLANS.

### TREE REMOVAL

THE DISTRICT FOUR TREE COMMITTEE SHOULD BE CONTACTED AND PRIOR APPROVAL OBTAINED FOR ANY TREE REMOVAL BEYOND THE LIMITS LOCATIONS INCLUDED IN THE PLANS.

### AGGREGATE SHOULDERS, TYPE B

AGGREGATE SHOULDERS, TYPE B SHALL BE REQUIRED FOR ALL GRANULAR CONSTRUCTION OF SIDE ROADS, ENTRANCES, AND MAILBOX TURNOUTS, WHETHER OR NOT PORTIONS OF THE SURFACES THUS CONSTRUCTED ARE TO BE COVERED WITH A BITUMINOUS SURFACE, EXCEPT WHERE NOTED DIFFERENTLY ON THE PLANS.

### ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

THE CONTRACTOR SHALL CONSULT WITH THE ENGINEER IN REGARD TO THE EXACT LENGTH OF THE BOXPIPE CULVERTS, STORM SEWERS, AND/OR PIPE DRAINS AS REQUIRED PRIOR TO ORDERING THESE ITEMS.

### COMMITMENTS

NO COMMITMENTS HAVE BEEN MADE FOR THIS PROJECT.

### STATUS OF UTILITIES

<u>STATION</u>	<u>OFFSET</u>	<u>ITEM</u>	<u>SURVEY NOTES</u>	<u>CONFLICT WITH</u>
199+46.25	50' RT	FO		PROPOSED MANHOLE
200+90.65	50' RT	FO		PROPOSED MANHOLE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## GENERAL NOTES AND COMMITMENTS

VERT. NONE  
SCALE: HORIZ. NONE  
DATE: 09/19/2008

DRAWN BY: BALSER  
DESIGNED BY: PETERSON  
CHECKED BY: BRUNER