

# SUMMARY OF QUANTITIES

URBAN  
100% STATE

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	IL 29 Y007	US 150 SFTY-2A
20400800	FURNISHED EXCAVATION	CY YD	166	111	55
20800150	TRENCH BACKFILL	CY YD	42	42	
21101615	TOPSOIL FURNISH <i>AND</i> PLACE, 4"	SQ YD	260	82	178
28000400	PERIMETER EROSION BARRIER	FOOT	500	150	350
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	22	22	
28200200	FILTER FABRIC	SQ YD	33	33	
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	106	106	
35501320	HOT - MIX ASPHALT BASE COURSE, 9"	SQ YD	106	106	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	0.44	0.44	
40600300	AGGREGATE (PRIME COAT)	TON	1.4	1.4	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	227	227	
40600990	TEMPORARY RAMP	SQ YD	38	38	
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	40	40	
44000100	PAVEMENT REMOVAL	SQ YD	106	106	
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	128	128	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	2		2
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	4	4	
54201285	PIPE CULVERTS, TYPE 2 RCCP 30"	FOOT	45		45
54209907	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE ROUND-SIZE 42"	FOOT	8	8	
54209913	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE ROUND-SIZE 48"	FOOT	48	48	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2		2
54214533	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 48"	EACH	1	1	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1	
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2		2
54248180	GRATING FOR CONCRETE FLARED END SECTION ROUND-SIZE 48"	EACH	1	1	
60220200	MANHOLES, TYPE A, 4'-DIAMETER EQUIVALENT	EACH	1	1	
60246805	MEDIAN INLET (604106)	EACH	2		2
60404400	FRAMES AND GRATES, TYPE 4	EACH	1	1	