CONTRACT NO. 76709

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-1A						X771-2A	I000-1A			
				I-70 & FRONTAGE RD	IL 162	I-70 & FRONTAGE RD	IL 162	IL 162 @ RAMPS & EAST FRONT. RD	IL 162 @ WEST FRONT. RD				I-55/70	IL 162
				ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.4	1.6			0.8							
40800030	AGGREGATE (PRIME COAT)	TON	3.8	2.6			1.2							
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	171	118			53							
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	36474			23628	12846							
42000516	PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4" (JOINTED)	SQ YD	7875				7875							
42001300	PROTECTIVE COAT	SQ YD	60864			35413	25451							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	1784			1016	768							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1305	1305										
44000100	PAVEMENT REMOVAL	SQ YD	62337	29336		20287	12714							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7476		7476									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5955	5387			568							
44000300	CURB REMOVAL	FOOT	537	499				38						
44000700	APPROACH SLAB REMOVAL	SQ YD	188				188							
44003100	MEDIAN REMOVAL	SQ FT	18316				18316							
44004000	PAVED DITCH REMOVAL	FOOT	181	181										
44004250	PAVED SHOULDER REMOVAL	SQ YD	14783	344	1288	11035	2116							
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1460		1460									
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	3507		639	2672	196							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4874	4225	649									
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	10986			10698	288							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1							1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	1		2								
50105220	PIPE CULVERT REMOVAL	FOOT	579	298		239	42							
50157300	PROTECTIVE SHIELD	SQ YD	1146							1146				
50200100	STRUCTURE EXCAVATION	CU YD	401							401				
50300225	CONCRETE STRUCTURES	CU YD	1977			33				770	1174			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	858							858				
50300260	BRIDGE DECK GROOVING	SQ YD	2935							2935				
50300300	PROTECTIVE COAT	SQ YD	5328							3456	1872			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1							1				
50500505	STUD SHEAR CONNECTORS	EACH	16981							16981				

PLOT DATE = 2/19/2009
FILE NAME = c:\pwidot\var\arcl\dms8941f\pln88083a.dgn
PLOT SCALE = 50.000 ' / IN.
REFERENCE = REF