CONTRACT NO. 76709

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-1A I-70 & FRONTAGE RD ROADWAY 100% FED	I000-1A IL 162 ROADWAY 100% FED	I000-1A I-70 & FRONTAGE RD ROADWAY 100% FED	I000-1A IL 162 ROADWAY 100% FED	I000-1A IL 162 @ RAMPS & EAST FRONT. RD TRAFFIC SIGNALS 100% FED	I000-1A IL 162 @ WEST FRONT. RD TRAFFIC SIGNALS 100% FED	X771-2A BRIDGE REPLACEMENT 100% FED	I000-1A MSE WALLS 100% FED	I000-1A SIGNING 100% FED	I000-1A I-55/70 HIGHWAY LIGHTING 100% FED	I000-1A IL 162 HIGHWAY LIGHTING 100% FED
50800105	REINFORCEMENT BARS	POUND	1980			1980								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	448220							322800	125420			
50800515	BAR SPLICERS	EACH	1239							1239				
50900105	ALUMINUM RAILING, TYPE L	FOOT	408							408				
51200957	FURNISHING METAL PILES SHELL 12" X 0.250"	FOOT	15910							15910				
51202305	DRIVING PILES	FOOT	15910							15910				
51203200	TEST PILE METAL SHELLS	EACH	3							3				
51205200	TEMPORARY SHEET PILING	SQ FT	3000							3000				
51500100	NAME PLATES	EACH	3							1	2			
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	524							524				
52100520	ANCHOR BOLTS, 1"	EACH	224							224				
52100530	ANCHOR BOLTS, 1 1/4"	EACH	52							52				
52100540	ANCHOR BOLTS, 1 1/2"	EACH	20							20				
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	8		8									
54020502	PRECAST CONCRETE BOX CULVERT 5' X 2' (M273)	FOOT	74				74							
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	313	42	96	90	85							
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	573	393		160	20							
54200436	PIPE CULVERTS, TYPE 1 RCCP 21"	FOOT	218	218										
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	57	32		25								
54200442	PIPE CULVERTS, TYPE 1 RCCP 27"	FOOT	600			600								
54200451	PIPE CULVERTS, TYPE 1 RCCP 36"	FOOT	32	32										
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	15	15										
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	9	9										
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	381			381								
54202119	PIPE CULVERTS, TYPE 3 RCCP 24"	FOOT	112			112								
54202950	PIPE CULVERTS, TYPE 4 RCCP 15"	FOOT	184			184								
54202959	PIPE CULVERTS, TYPE 4 RCCP 24"	FOOT	507			507								
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	14			7	7							
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	12	2	2	2	6							
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	23	5		16	2							

PLOT DATE = 2/10/2009
FILE NAME = c:\pw_work\PWIDOT\KERLARCL\dms80415\sht89803a.dgn
PLOT SCALE = 50.000 ' / IN.
REFERENCE = REF