

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

I000-1A

X711-2A

I000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	1829	33		308	1488								
58700300	CONCRETE SEALER	SQ FT	1415						1415						
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4			4									
60107600	PIPE UNDERDRAINS 4"	FOOT	5950			5950									
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	82			82									
60221700	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 8 GRATE	EACH	2			2									
60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	2	2											
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6	2			4								
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	7			7									
60240225	INLETS, TYPE B, TYPE 4 FRAME AND GRATE	EACH	2	2											
60255500	MANHOLES TO BE ADJUSTED	EACH	4	2			2								
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3				3								
60405900	GRATES AND COVERS, TYPE 2B	EACH	1				1								
60500060	REMOVING INLETS	EACH	8	4			4								
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	30				30								
60600605	CONCRETE CURB, TYPE B	FOOT	332	322			10								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2890				2890								
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	162				162								
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	2232				2232								
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	1569				1569								
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	21141				21141								
60624600	CORRUGATED MEDIAN	SQ FT	1200				1200								
60900515	CONCRETE THRUST BLOCKS	EACH	13			7	6								
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1287.5			1287.5									
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6			6									
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6			6									
63200310	GUARDRAIL REMOVAL	FOOT	2226			1966	260								
63500105	DELINEATORS	EACH	91			91									
63500120	DELINEATOR REMOVAL	EACH	56			56									
66500105	WOVEN WIRE FENCE, 4'	FOOT	5371	4981		390									

\*Specialty Items

PLOT DATE = 2/19/2009  
 FILE NAME = c:\pva\work\pva\p1001\VEPR\ARCL\Name88415.plt\_080203a.dgn  
 PLOT SCALE = 500000 / 1 IN.  
 REFERENCE = 0