

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

I 000-1A

X171-2A

I 000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
86400100	TRANSCEIVER - FIBER OPTIC	EACH						2	1						
87100140	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 12F	FOOT						2180							
87300815	ELECTRIC CABLE IN TRENCH, SERVICE, NO. 6 3 C	FOOT					650	300							
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT					10133	3126							
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT					1865	1667							
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT					6317	1680							
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH					6	3							
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH					2								
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH					1	1							
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH					1	1							
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH					1	1							
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH					1	1							
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT					36	18							
87800200	CONCRETE FOUNDATION, TYPE D	FOOT					8	4							
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT					20								
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT					56	56							
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH					28	7							
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH					8	6							
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH					4	4							
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH					4	4							
88200100	TRAFFIC SIGNAL BACKPLATE	EACH					32	11							
88500100	INDUCTIVE LOOP DETECTOR	EACH					44	14							
89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM					0.5	0.5							
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH					9								
89502380	REMOVE EXISTING HANDHOLE	EACH					10								

*Specialty Items

PLOT DATE = 2/18/2009
 FILE NAME = C:\p100\user\arcl\dms88415\p1008826.dgn
 SHEET NO. = 13
 REFERENCE = *REF*