

(CONTINUED)

CLASS SI CONCRETE (OUTLET)

LOCATION	CU YD
WEST FRONTAGE ROAD	
17+73.45 RT	4.14
18+82.00 LT	2.07
20+68.80 LT	3.51
21+15.00 RT	4.14
EAST FRONTAGE ROAD	
33+77.30 LT	4.14
33+94.20 RT	3.86
35+90.00 RT	3.65
36+64.40 LT	4.14
TOTAL	29.7

GRATES AND COVERS, TYPE 2B

LOCATION	EACH
IL ROUTE 162	
491+13.40 RT	1
TOTAL	1

PLAN SURVEYED BY DATE
 ALIGNED BY
 NOTE BOOK NO. OF WAY CHECKED
 CADD FILE NAME

Location	Structure No.	INLETS, TYPE A				INLETS, TYPE B		MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	FLARED END SECTIONS				FLARED END SECTIONS W/ GRATING		METAL END SECTION		RC END SECTION STD. 542116 (*)				INLET BOX STD. 542531	END SECTION W/ GRATING			CONCRETE STRUCTURES	REINFORCEMENT BARS
		TYPE 3V FRAME AND GRATE	TYPE 8 GRATE	TYPE 20 FRAME AND GRATE	TYPE 4 FRAME AND GRATE	TYPE 3V FRAME AND GRATE	TYPE 4 FRAME AND GRATE		12"	15"	18"	24"	27"	36"	18"	24"	15"	18"	21"	24"		24"	6'x4'	5'x2'		
Ramp C																										
24+50.00				1																						
25+30.80																										
25+52.40																										
Ramp D																										
12+34.00																										
12+56.30																										
13+00.00				1																						
14+42.00				1																						
I-70																										
1347+68.00																										
1347+67.00																										
1348+00.00																										
1355+69.78																										
1356+01.30																										
1356+32.73																										
TOTAL=		6	6	7	2	6	2	2	14	12	5	2	6	1	2	1	2	4	6	10	6	1	1	1	33.0	1980

(*) PAID AS CONCRETE STRUCTURES AND REINFORCEMENT BARS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES
DRAINAGE - 3**

DRAWN BY: GRH

PLOT DATE: *DATE-TIME*

DUAL-LINE
 NON-SPEC
 REF