

SUMMARY OF QUANTITIES

URBAN

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	CONSTRUCTION TYPE CODE	
		UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	865
20800150	TRENCH BACKFILL	CU YD	167
25000210	SEEDING, CLASS 2A	ACRE	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8
25100115	MULCH, METHOD 2	ACRE	0.4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80
28000300	TEMPORARY DITCH CHECKS	EACH	2
28000400	PERIMETER EROSION BARRIER	FOOT	1682
28000500	INLET AND PIPE PROTECTION	EACH	8
28000720	MULCH, METHOD 2	ACRE	0.4
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	4849
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	4296
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.3
40600300	AGGREGATE (PRIME COAT)	TON	48.8
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1153
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	61
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	267
40600990	TEMPORARY RAMP	SQ YD	740
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1761
44000100	PAVEMENT REMOVAL	SQ YD	471
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	16741
44003100	MEDIAN REMOVAL	SQ FT	17354
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	1003
44004250	PAVED SHOULDER REMOVAL	SQ YD	2335
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	334
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1037
48203100	HOT-MIX ASPHALT SHOULDERS	TON	329
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	46
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	250
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	2
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2
60261500	INLETS TO BE ADJUSTED WITH NEW TYPE 15 FRAME AND LID	EACH	1

SUMMARY OF QUANTITIES

URBAN

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	CONSTRUCTION TYPE CODE	
		UNIT	QUANTITY
60267155	FLUSH INLET BOX FOR MEDIAN (542546) TO BE RECONSTRUCTED	EACH	1
60401040	FRAMES, TYPE 24	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	75
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	19364
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1320
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	22150
70300250	TEMPORARY PAVEMENT MARKING-LINE 8"	FOOT	2618
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	978
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	226
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18566
* 72000200	SIGN PANEL - TYPE 2	SQ FT	32
* 73000100	WOOD SIGN SUPPORT	FOOT	30
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	12408
* 78000500	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	FOOT	2618
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	978
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	204
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	301
* 78200300	PRISMATIC CURB REFLECTOR	EACH	105
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1264
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	170
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	200
* 80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	14
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	14
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	1250
* 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	13
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	61
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	28
* 81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	70

FILE NAME =
#FILE#

USER NAME = #USER#
PLOT SCALE = #SCALE#
PLOT DATE = #DATE#

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 58 SHEETS STA. TO STA.

F.A.P. RTE. 674 SECTION 410-1-N COUNTY ST. CLAIR TOTAL SHEETS 58 SHEET NO. 3 CONTRACT NO. 76C63
*Specialty Items
ILLINOIS FED. AID PROJECT