

SUMMARY OF QUANTITIES

		URBAN	
		CONSTRUCTION TYPE CODE	
		1000-1A	
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	QUANTITY
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	8
81013100	CONDUIT IN TRENCH, 5" DIA., PVC	FOOT	23
81018200	CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	48
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	235
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	40
81018800	CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	149
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	62
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	95
81400100	HANDHOLE	EACH	11
81400300	DOUBLE HANDHOLE	EACH	1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1481
85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
85706000	INTERSECTION MONITOR UNIT	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6433
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1702
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6661
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	14
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	41
87900200	DRILL EXISTING HANDHOLE	EACH	4
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8
88500100	INDUCTIVE LOOP DETECTOR	EACH	17
88600100	DETECTOR LOOP, TYPE I	FOOT	1466
89000105	TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL)	EACH	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
89502380	REMOVE EXISTING HANDHOLE	EACH	9
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8

\*

\*Specialty Items  
© 1980

SUMMARY OF QUANTITIES

		URBAN	
		CONSTRUCTION TYPE CODE	
		1000-1A	
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	QUANTITY
* X7240500	RELOCATE EXISTING SIGNS	EACH	3
* X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SO FT	316
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	976
© Z0076600	2 TRAINEES	HOURS	1,000