SCHEDULE
EARTHWORK

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
IL. 158				
STA. 233+75 TO STA. 245+00	712	534	594	-60
STA. 247+00 TO STA. 248+25	90	68	35	+33
SEIBERT RD.				
STA. 1110+00 TO STA. 1114+50	38	29	2	+27
STA. 1116+50 TO STA. 1119+50	25	19	19	0
TOTAL	865	650	650	0

SCHEDULE
TRENCH BACKFILL

LOCATION	QUANTITY (CU. YD.)
STA. 240+09 TO STA. 242+02	159.0
STA. 1113+00	2.0
STA. 1114+33 TO STA. 1114+68	6.0
TOTAL	167.0

SCHEDULE
BASE COURSE

LOCATION	PCC BASE COURSE, 8" (SQ. YD.)	AGG. BASE COURSE, TY. A 4" (SQ. YD.)
STA. 233+87.4 LT. TO STA. 1117+60.7 LT.	1478	1690
STA. 235+61.5 RT. TO STA. 244+53.7 LT.	1644	1794
STA. 1110+72.9 TO STA. 1114+72	406	475
STA. 1113+55.5 RT. TO STA. 247+74.5 RT.	118	151
STA. 248+10.3 LT. TO STA. 1117+49.3 RT.	300	341
STA. 1116+00 TO STA. 1119+02.5	350	398
TOTAL	4296	4849

SCHEDULE
EROSION CONTROL ITEMS

LOCATION	PERIMETER EROSION BARRIER (FT.)	TEMP. DITCH CHECK (EACH)	TEMP. EROSION CONTROL SEEDING (POUND)	INLET AND PIPE PROTECTION (EACH)
STA. 235+50 TO STA. 240+11			80	
STA. 237+00 LT.		1		
STA. 239+00 LT.		1		
STA. 233+75 TO STA. 245+55 LT	1260			
STA. 1113+45 TO STA. 1114+57 RT.	185			
STA. 1116+24 TO STA. 1117+60 RT.	237			
STA. 239+50 LT.				1
STA. 242+00				1
STA. 245+50 LT.				1
STA. 245+72 RT.				1
STA. 1113+00.5				2
STA. 1114+33 LT.				1
STA. 1114+68.3 RT.				1
TOTAL	1682	2	80	8

SCHEDULE
PERMANENT SEEDING

LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUT. (POUND)	PHOSPHORUS FERT. NUT. (POUND)	POTASSIUM FERT. NUT. (POUND)	MULCH METHOD 2 (ACRE)	AGRICULTURAL GROUND LIMESTONE (TON)
STA. 235+50 TO STA. 240+11 (CEN. MED.)	0.4	36	36	36	0.4	0.8
TOTAL	0.4	36	36	36	0.4	0.8

SCHEDULE
PAINT PAVEMENT MARKING - RAISED MEDIAN

LOCATION	QUANTITY (SQ. FT.)
IL. 158	
STA. 242+37 RT.	35
STA. 245+55 LT.	24
STA. 246+92 RT.	45
SEIBERT RD.	
STA. 1110+19 LT.	20
STA. 1114+48 LT.	24
STA. 1116+27 RT.	24
N.E. ISLAND	36
S.E. ISLAND	36
S.W. ISLAND	36
N.W. ISLAND	36
TOTAL	316

SCHEDULE
RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	RAISED REFL PAVT MRK REM (EACH)	RAISED REFL PAVT MRK (EACH)
IL. 158		
STA. 233+75 TO STA. 248+25	150	204
SEIBERT RD.		
STA. 1110+00 TO STA. 1115+35.19	20	97
TOTAL	170	301

SCHEDULE
PRISMATIC CURB REFLECTOR

LOCATION	QUANTITY (EACH)
IL. 158	
STA. 240+11.8 TO STA. 245+56 LT.	30
SEIBERT RD.	
STA. 1110+19.2 TO STA. 1114+47.9 LT.	28
STA. 1116+26.5 TO STA. 1119+38.6	18
N.W. CORNER ISLAND	7
S.W. CORNER ISLAND	10
S.E. CORNER ISLAND	12
TOTAL	105

SCHEDULE
PAINT PAVEMENT MARKING CURB

LOCATION	QUANTITY (FOOT)
IL. 158	
STA. 240+11 TO STA. 240+75 LT.	48
STA. 242+37 TO STA. 243+73 RT.	116
STA. 244+80 TO STA. 245+55 LT.	68
STA. 245+64 TO STA. 245+75 RT.	40
STA. 246+64 TO STA. 246+74	55
STA. 246+92 TO STA. 247+02 RT.	68
SEIBERT RD.	
STA. 1110+19 TO STA. 1110+94 LT.	68
STA. 1113+73 TO STA. 1114+48 LT.	68
STA. 1116+27 TO STA. 1117+00 RT.	68
N.E. ISLAND	124
S.E. ISLAND	111
S.W. ISLAND	72
N.W. ISLAND	70
TOTAL	976

SCHEDULE
PAVEMENT MARKING

LOCATION	THERMOPLASTIC PAVEMENT MARKING							TEMPORARY PAVEMENT MARKING					SHORT-TERM PVMT. MRK. LINE	WORK ZONE PVMT. MRK. REMOVAL	PAVEMENT MARKING REMOVAL	SIGN PANEL - TYPE 2	WOOD SIGN SUPPORT
	SOLID 4"	SKIP-DASH (2'/6') WHITE 4"	SKIP-DASH (10'/30') WHITE 4"	SOLID 8"	SOLID 12"	SOLID WHITE 24"	LETTERS & SYMBOLS	LINE 4"	LINE 8"	LINE 12"	LINE 24"	LETTERS & SYMBOLS					
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	SQ. FT.	SQ. FT.	SQ. FT.	FOOT
IL. 158																	
STA. 233+75 TO STA. 248+25	4651	98	940	1574	285	87	93.6	5689	1574	285	87	93.6	798	7256			
SEIBERT RD.																	
STA. 1105+05 TO STA. 1114+80	4220	34	120	350	258	66	31.2	4374	350	258	66	31.2	260	4312			
STA. 1115+80 TO STA. 1120+00	2155		190	694	435	51	31.2	2345	694	435	51	31.2	262	3710			
STAGE I								2476						825	492		
STAGE III								5715						1903	701		
STAGE IV								1551			22			560	71		
STA. 237+30 RT. (W4-2) 48"																16	15
STA. 240+98 RT. (W9-1) 48"																16	15
SUB-TOTAL	11026	132	1250														
TOTAL		12408		2618	978	204	156	22150	2618	978	226	156	1320	18566	1264	32	30

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. 8 OF 58 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
674	410-1-N	ST. CLAIR	58	8
		CONTRACT NO. 76C63		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		