SCHEDULE
PAVEMENT

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	LEVELING BINDER (MACHINE METHOD) N90	HMA SURF. CRSE. MIX D N90	TEMPORARY RAMP
	TON	TON	TON	TON	SQ. YD.
STA. 233+75 TO STA. 234+25 (N.B.)	0.07	0.37		15.8	
STA. 234+25 TO STA. 236+00 (N.B.)	0.29	1.53	33.6	50.4	
STA. 235+50 TO STA. 236+00 (S.B.)	0.08	0.42		16.4	
STA. 236+00 TO STA. 242+37 (N.B./S.B.)	3.12	16.42	367.0	550.5	
STA. 242+37 TO STA. 245+77 (N.B./S.B.)	1.91	10.03	251.8	377.7	
STA. 246+63 TO STA. 248+00 (N.B./S.B.)	0.71	3.72	92.7	139.1	
STA. 248+00 TO STA. 248+25 (N.B.)	0.04	0.24	5.2	7.7	
STA. 1110+00 TO STA. 1114+64 (E.B./W.B.)	1.26	6.63	167.5	251.3	
STA. 1114+64 TO STA. 1116+00 (E.B./W.B.)	0.60	3.15	88.2	132.2	
STA. 1116+00 TO STA. 1119+50 (E.B./W.B.)	1.19	6.26	146.6	219.9	
STAGE I					240
STAGE II					300
STAGE III					200
TOTAL	9.3	48.8	1153	1761	740

SCHEDULE
PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STA. 243+00 TO STA. 245+57 (E. MED.)	78.0
STA. 245+01 TO STA. 245+77 (W. MED.)	6.0
STA. 1110+14 TO STA. 1114+72 (CEN. MED.)	106.0
STA. 1114+43 TO STA. 1114+69 (N.W.)	21.5
STA. 1114+47 TO STA. 1114+72 (S.W.)	39.0
STA. 1116+00 TO STA. 1119+39 (CEN. MED)	93.5
STA. 1116+02 TO STA. 1119+49 (S.E.)	127.00
TOTAL	471.0

SCHEDULE
PAVED SHOULDER REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STA. 233+87.4 TO STA. 245+78.5 LT.	1427
STA. 235+61.5 TO STA. 243+27 RT.	495
STA. 1113+55.5 TO STA. 1114+80.5 RT.	126
STA. 1116+00 TO STA. 1117+49.3	287
TOTAL	2335

SCHEDULE
MEDIAN REMOVAL

LOCATION	QUANTITY (SQ. FT.)
STA. 243+04 TO STA. 245+56 (E. MED.)	3358
STA. 245+01 TO STA. 245+76 (W. MED.)	192
STA. 1110+15 TO STA. 1114+71 (CEN. MED.)	7067
STA. 1114+69 TO STA. 1114+67 (N.W.)	188
STA. 1114+62 TO STA. 1114+69 (S.W.)	35
STA. 1116+01 TO STA. 1119+39 (CEN. MED.)	6337
STA. 1116+04 TO STA. 1116+21 (S.E.)	177
TOTAL	17354

SCHEDULE
HMA SURFACE REMOVAL 2 1/2"

LOCATION	QUANTITY (SQ. YD.)
STA. 237+70 TO STA. 242+37 (N.B./S.B.)	4062.8
STA. 242+37 TO STA. 245+77 (N.B./S.B.)	4140.6
STA. 246+63 TO STA. 248+00 (N.B./S.B.)	1316.1
STA. 248+00 TO STA. 248+25 (N.B.)	106.6
STA. 1110+00 TO STA. 1114+64 (E.B./W.B.)	2955.9
STA. 1114+64 TO STA. 1116+00 (E.B./W.B.)	1229.1
STA. 1116+00 TO STA. 1119+50 (E.B./W.B.)	2929.9
TOTAL	16741

SCHEDULE
COMB. CONC. CURB & GUTTER, TY. B-6.24

LOCATION	QUANTITY (FOOT)
STA. 245+00 TO STA. 245+76.8	75
TOTAL	75

SCHEDULE
CONC. MEDIAN, TY. SB-6.24

LOCATION	QUANTITY (SQ. FT.)
STA. 240+11.8 TO STA. 245+56.8	9370
STA. 1110+14.4 TO STA. 1114+68	4298
STA. 1114+43.2 TO STA. 1114+69.3 (N.W.)	384
STA. 1114+46.6 TO STA. 1114+72 (S.W.)	387
STA. 1116+01 TO STA. 1116+44 (S.E.)	984
STA. 1116+00 TO STA. 1119+38.6 (CEN. MED.)	3941
TOTAL	19364

SCHEDULE
STORM SEWER

LOCATION	STORM SEWER CL. A, TY. 2 18"	STORM SEWER CL. A, TY. 2 24"	INLETS, TY. B, TY. 15 FRAME AND LID	INLETS TO BE ADJUSTED W/ NEW TY. 1 FRAME, OPEN LID	INLETS TO BE ADJUSTED W/ NEW TY. 15 FRAME AND LID	FLUSH INLET BOX FOR MEDIAN, STD. 524546	FLUSH INLET BOX FOR MEDIAN (524546) TO BE RECONSTRUCTED	FRAMES, TYPE 24
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
STA. 239+50, 15.3' LT.						1		
STA. 239+50 TO STA. 242+00		250						
STA. 242+00							1	1
STA. 245+50 LT.					1			
STA. 1113+00.5	10		1	1				
STA. 1114+32.94 LT.			1					
STA. 1114+32.94 TO STA. 1114+68.3	36							
STA. 1114+68.3				1				
TOTAL	46	250	2	2	1	1	1	1

SCHEDULE
HOT-MIX ASPHALT SHOULDERS, 8"

LOCATION	QUANTITY (SQ. YD.)
IL. 158	
STA. 233+87.4 TO STA. 245+76.53 (N.B./E.)	608.8
STA. 235+61.5 TO STA. 240+11.61 (S.B./E.)	201.3
SEIBERT RD.	
STA. 1113+55.5 TO STA. 1114+78.5 (S.W. CORN)	92.6
STA. 1116+01.4 TO STA. 1117+49.25 (S.E. CORN)	134.2
TOTAL	1036.9

SCHEDULE
HOT-MIX ASPHALT SHOULDERS

LOCATION	QUANTITY (TON)
IL. 158	
STA. 233+75 TO STA. 233+87.35 (N.B./E. & W.)	3.0
STA. 233+87.35 TO STA. 235+61.45 (N.B./W.)	15.1
STA. 235+50 TO STA. 235+61.45 (N.B./W., S.B./E.&W.)	3.8
STA. 235+61.45 TO STA. 240+11.82 (N.B./W., S.B./W.)	110.5
STA. 240+11.82 TO STA. 245+60 (S.B./W.)	81.3
STA. 247+74.47 TO STA. 248+00 (S.B./W.)	4.0
STA. 248+10.3 TO STA. 248+25 (N.B./E.)	2.3
SEIBERT RD.	
STA. 1110+00 TO STA. 1113+55.5 (N. & S.)	43.8
STA. 1113+55.5 TO STA. 1114+27.5 (N.)	4.5
STA. 1117+49.3 TO STA. 1117+60.7 (S.)	1.8
STA. 1117+60.7 TO STA. 1119+50 (N. & S.)	58.9
TOTAL	329

SCHEDULE
AGGREGATE WEDGE SHOULDER, TYPE B

LOCATION	QUANTITY (TON)
IL. 158	
STA. 233+75 TO STA. 235+50 (N.B./E. & W.)	15.5
STA. 235+50 TO STA. 240+11.6 (N.B./S.B., E. & W.)	81.8
STA. 240+11.6 TO STA. 245+60 (N.B./E. & S.B./W.)	50.9
STA. 235+61.45 TO STA. 240+11.82 (N.B./W., S.B./W.)	110.5
STA. 246+77 TO STA. 248+00 (N.B./E. & S.B./W.)	13.1
STA. 248+00 TO STA. 248+25 (N.B./E.)	1.1
SEIBERT RD.	
STA. 1110+00 TO STA. 1114+24 (N. & S.)	37.7
STA. 1116+87 TO STA. 1119+50 (N. & S.)	22.9
TOTAL	334

SCHEDULE
SURFACE REMOVAL - BUTT JOINT

LOCATION	HMA (SQ. YD.)	PCC (SQ. YD.)
STA. 233+75 TO STA. 234+25 (N.B.)	47	133.5
STA. 235+50 TO STA. 236+00 (S.B.)	14	133.5
TOTAL	61	267

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
674	410-1-N	ST. CLAIR	57	9
		CONTRACT NO. 76C63		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		