

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 90% FED 10% STATE	-----	-----	CODE NO	ITEM	UNIT		-----	-----	-----
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	12.6	12.6									
40600300	AGGREGATE (PRIME COAT)	TON	60	60									
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3383	3383									
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	2255	2255									
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	20137	20137									
44200629	CLASS A PATCHES, TYPE I, 15 INCH	SQ YD	24	24									
44200630	CLASS A PATCHES, TYPE II, 15 INCH	SQ YD	80	80									
44200631	CLASS A PATCHES, TYPE III, 15 INCH	SQ YD	144	144									
44201027	CLASS B PATCHES, TYPE I, 15 INCH	SQ YD	24	24									
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	80	80									
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	144	144									
44213000	PATCHING REINFORCEMENT	SQ YD	248	248									
44213100	PAVEMENT FABRIC	SQ YD	248	248									
44213200	SAW CUTS	FOOT	2627	2627									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6									
67100100	MOBILIZATION	L SUM	1	1									
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	27	27									
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1									
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1									
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3868	3868									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19343	19343									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1289	1289									
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19343	19343									
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	507	507									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	507	507									
Z0017202	DOWEL BARS 1 1/2"	EACH	360	360									
Z0075310	TIE BARS 3/4"	EACH	240	240									
© Z0076600	TRAINNEES	HOOR	500	500									

© Y080

*Specialty Items

FILE NAME =	USER NAME = bergmd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pw\work\VPWIDOT\BERGMD\0120423\08764	94-aht-plan.dgn	DRAWN -	REVISED -			55	60-(1,2,3)-1	MADISON	14	3	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			
	PLOT DATE = 3/18/2009	DATE -	REVISED -			CONTRACT NO. 76C94					