

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, SIGNATURE BLOCK, GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTION
5	PLAN SHEET
6	DETAILS
7	CROSS SECTION

HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
442201-03	CLASS C AND D PATCHES
483001-04	PCC SHOULDER
542106-02	REINFORCED CONCRETE END SECTIONS FOR PIPE CULVERT
630001-08	STEEL PLATE BEAM GUARDRAIL
701201-03	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
701206-02	LANE CLOSURE, 2L, 2W, NIGHT ONLY, FOR SPEEDS > 45 MPH
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
BLR 17-4	TRAFFIC CONTROL DEVICES-DAY LABOR CONSTRUCTION
BLR 22-6	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

COMMITMENTS

NONE AT THIS TIME

Prepared By: *Joe G. Blawie*  
 DISTRICT STUDIES & PLANS ENGINEER

Examined By: *[Signature]*  
 DISTRICT LAND ACQUISITION ENGINEER

Examined By: *Carrie Nelson*  
 DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By: *[Signature]*  
 DISTRICT OPERATIONS ENGINEER

Examined By: *[Signature]*  
 DISTRICT CONSTRUCTION ENGINEER

Examined By: *Bruce DeBlor*  
 DISTRICT MATERIALS ENGINEER

Examined By: *[Signature]*  
 DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: *Danny Clayton*  
 ASSISTANT REGIONAL ENGINEER

Approved By: *Mary C. Lammie*  
 DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER

March 26 2009  
 DATE

GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL AGGREGATE  
 2.05 TONS/CU. YD.

RIPRAP  
 1.50 TONS/CU. YD.

ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE LEFT IN PLACE UNTIL REMOVAL IS REQUIRED TO CONSTRUCT FINAL GRADE LINES.

AREAS OF EXISTING AGGREGATE SHOULDERS THAT SHALL BE REMOVED FOR CONSTRUCTION SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR PIPE CULVERTS, CLASS A.

PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION OR A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR, HOWEVER, WILL BE PAID FOR THE ACTUAL QUANTITY FURNISHED AT THE UNIT PRICE BID FOR THE WORK. CONSTRUCTION PLANS ARE AVAILABLE FOR REVIEW AT THE DISTRICT 9 HEADQUARTERS IN CARBONDALE, ILLINOIS.

ALL EARTH EXCAVATION SHALL BE INCLUDED IN THE COST OF PIPE CULVERTS, CLASS A