



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2009

SUBJECT: RIVERFRONT TRAIL
Project HPP-4101(003)
Section 06-00001-00-BT (Kankakee)
Kankakee County
Contract No. 87390
Item 64
June 12, 2009 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Revised page 2 of the special provisions

Plans – Revised sheet 14

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger DE".

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

SEEDING, CLASS 1B (CONT.)

The Contractor shall clean up all work areas to the "before construction" conditions. The Engineer shall be the sole judge of the completeness of the clean-up efforts. All labor and materials necessary to this restoration will be considered incidental to the contract.

This item will be paid at the contract unit price per acre for SEEDING, CLASS 1B. This price shall include all work necessary to complete the work described above.

STONE RIPRAP, CLASS A4

Stone Riprap, Class A4 shall be quality A as specified in Article 1005.01.

DETECTABLE WARNINGS

This item of work shall conform to Section 424 of the Standard Specifications and the Bureau of Design and Environment Special Provisions except as herein modified.

The Detectable Warnings shall consist of a pre-cast panel or panels meeting these requirements. The panel(s) shall be set into the concrete sidewalk and shall have a minimum of two inches of concrete below the panel, but the total thickness shall be not less than four inches. The panel(s) surface shall be protected during installation to prevent concrete from coming into contact with the detectable warning.

This item will be paid for per the Contract unit price per Square Foot for DETECTABLE WARNINGS. The price shall be full compensation for furnishing all materials, for all preparation and for all labor, equipment, tools, and incidentals necessary to complete this item.

HANDRAIL REMOVAL

The existing handrails shall be removed completely. This shall include the removal of rails, posts, bases and anchors. Anchors set in the concrete shall be cut flush with the concrete surface after removal of the railing.

CHAIN LINK FENCE, 6'

Chain link fence shall be installed in accordance with Specification Section 664 except as modified below. The existing concrete pillars from the original fence line in the Shapiro Developmental Center shall be used. Connection to the existing concrete pillars shall be made in a similar manner as the original connections. Any additional materials and labor required to reuse the existing concrete pillars is incidental to the item "CHAIN LINK FENCE, 6'" and no additional compensation will be made.

Any clearing of brush along the fence line necessary for the installation shall be incidental to the item "CHAIN LINK FENCE, 6'" and no additional compensation will be made.

Revised 6-1-09
E07093