

LANDSCAPING SCHEDULE				SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 1
LOCATION	LENGTH	WIDTH	ACRE	POUND	POUND	POUND	ACRE	
STA. 1+08.00 TO 2+89.30	181.3	11.0	0.05	4.12	4.12	4.12	0.05	
STA. 3+04.30 TO 7+06.70	402.4	11.0	0.10	9.15	9.15	9.15	0.10	
STA. 7+36.70 TO 11+08.00	371.3	11.0	0.09	8.44	8.44	8.44	0.09	
STA. 11+94.00 TO 15+67.00	373	11.0	0.09	8.48	8.48	8.48	0.09	
STA. 16+24.00 TO 19+90.00	366	11.0	0.09	8.32	8.32	8.32	0.09	
TOTAL			0.50	39.0	39.0	39.0	0.50	

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH						
LOCATION	LENGTH	WIDTH	SQ FT			
STA. 1+08.00 TO 2+89.30	181.3	* 6.0	1087.8			
STA. 3+04.30 TO 3+50.00	45.7	* 6.0	274.2			
STA. 4+58.00 TO 7+06.70	248.7	* 6.0	1492.2			
STA. 7+36.70 TO 11+08.00	371.3	* 6.0	2227.8			
STA. 11+94.00 TO 15+67.00	373.0	* 6.0	2238.0			
STA. 16+24.00 TO 17+60.00	136.0	* 6.0	816.0			
STA. 17+80.00 TO 19+90.00	210.0	* 6.0	1260.0			
STA. 2+00.00 TO 2+10.00	10.0	* 17.0	170.0			
TOTAL			9566.0			

PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL						
LOCATION	LENGTH	WIDTH	SQ FT			
STA. 11+08.00 TO 11+37.00	29.0	* 6.0	174.0			
STA. 11+53.00 TO 11+70.00	17.0	* 6.0	102.0			
STA. 17+60.00 TO 17+80.00	20.0	* 6.0	120.0			
STA. 19+90.00 TO 20+36.00	46.0	* 6.0	276.0			
TOTAL			672.0			

PORTLAND CONCRETE CEMENT SIDEWALK, 8 INCH						
LOCATION	LENGTH	WIDTH	SQ FT			
STA. 3+50.00 TO 4+58.00	108.00	* 6.0	648.0			
TOTAL			648.0			

LOCATION		PCC DRIVEWAY PVM'T, 8 INCH	PVMT PATCH (FD)
LOCATION	WIDTH	SQ YD	SQ YD
STA. 2+96.80 RT.	15.0	38.0	1.7
STA. 7+21.70 RT.	30.0	68.0	3.3
STA. 11+82.00 RT.	24.0	80.0	2.7
TOTAL		186.0	8.0

AGGREGATE WEDGE SHOULDER, TYPE B				
LOCATION	LENGTH	WIDTH	TONS	
STA. 1+08.00 TO 2+89.30	181.3	2.0	5.4	
STA. 3+04.30 TO 7+06.70	402.4	2.0	12.1	
STA. 7+36.70 TO 11+08.00	371.3	2.0	11.1	
STA. 11+94.00 TO 15+67.00	373	2.0	11.2	
STA. 16+24.00 TO 19+90.00	366	2.0	11.0	
TOTAL		1694	51.0	

TREE REMOVAL (OVER 15 UNITS DIAMETER)		
LOCATION	UNITS	
STA. 3+25.00 , 25.0 RT.	24	
TOTAL 24		

CONCRETE RETAINING WALL REMOVAL		
LOCATION	FOOT	
STA. 17+70.60 , 23.7 RT. TO 17+82.20 , 23.7 RT.	11.6	
TOTAL 11.6		

SIGN PANEL - TYPE 1		
LOCATION	SQ FT	
W11A-2 - STA. 0+50	4	
W11A-2 - STA. 4+50	4	
TOTAL 8		

TELESCOPING STEEL SIGN SUPPORT		
LOCATION	FOOT	
W11A-2 - STA. 0+50	15	
W11A-2 - STA. 4+50	15	
TOTAL 30		

PEDESTRIAN RAILING		
LOCATION	FOOT	
STA. 3+50.00 , 28.5' RT. TO 4+58.00 , 28.5' RT.	108.0	
STA. 3+50.00 , 23.5' RT. TO 4+58.00 , 23.5' RT.	108.0	
STA. 11+08.00 , 28.5' RT. TO 11+37.00 , 28.5' RT.	29.0	
STA. 11+37.00 , 28.5' RT. TO 11+53.00 , 28.5' RT.	16.0	
STA. 11+53.00 , 28.5' RT. TO 11+58.00 , 28.5' RT.	5.0	
TOTAL 266		

SPECIAL STRUCTURE SP-1		
LOCATION	EACH	
STA. 11+37.00 TO 11+53.00	1	
TOTAL 1		

TRAFFIC CONTROL COMPLETE		
LOCATION	L SUM	
JOBSITE	1	
TOTAL 1		

MOBILIZATION		
LOCATION	L SUM	
JOBSITE	1	
TOTAL 1		

DETECTABLE WARNINGS		
LOCATION	SQ FT	
STA. 15+67±, RT.	8	
STA. 16+24±, RT.	8	
STA. 20+36±, RT.	8	
TOTAL 24		

PAINT PAVEMENT MARKING - LINE 24"		
LOCATION	FOOT	
STA. 15+94.50 , 34.5 RT. TO 16+17.50 , 34.5 RT.	23.0	
STA. 20+54.50 , 34.5 RT. TO 20+72.30 , 34.5 RT.	17.8	
TOTAL 41.0		

PAINT PAVEMENT MARKING - LINE 6"		
LOCATION	FOOT	
STA. 1+99.70 , 6.2 RT. TO 1+99.70 , 19.2 LT.	25.4	
STA. 2+10.20 , 6.3 RT. TO 2+10.20 , 19.1 LT.	25.4	
STA. 15+67.00 , 29.3 RT. TO 16+23.00 , 29.3 RT.	56.0	
STA. 15+64.20 , 22.8 RT. TO 16+28.40 , 22.8 RT.	64.2	
STA. 20+30.80 , 22.8 RT. TO 20+80.80 , 22.8 RT.	50.0	
STA. 20+35.80 , 29.3 RT. TO 20+74.60 , 29.3 RT.	38.8	
TOTAL 260.0		

FILE NAME = X:\P\1512\2009\0800002.dwg; P:\1512\2009\05_02_M-SCHEDULE OF QUANTITIES.dgn



USER NAME = csl	DESIGNED -	REVISED -
PLOT SCALE = 1/8" = 1' IN.	DRAWN -	REVISED -
PLOT DATE = 4/7/2009	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF
QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				08-00000-00-SW	WOODFORD	21	6
						CONTRACT NO. 89503	
ILLINOIS FED. AID PROJECT							