

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	08-00048-00-BT	SHELBY	29	2.

\*\* GENERAL DACEY TRAIL

**SUMMARY OF QUANTITIES**

PAY ITEM CODE	DESCRIPTION	QUANTITY	UNIT
20100500	TREE REMOVAL, ACRES	0.40	ACRE
20200100	EARTH EXCAVATION	1113	CU YD
20400800	FURNISHED EXCAVATION	3001	CU YD
25000200	SEEDING, CLASS 2	1.2	ACRE
25000310	SEEDING, CLASS 4	0.4	ACRE
25000400	NITROGEN FERTILIZER NUTRIENT	108	POUND
25000500	PHOSPHORUS FERTILIZER NUTRIENT	108	POUND
25000600	POTASSIUM FERTILIZER NUTRIENT	108	POUND
25100115	MULCH, METHOD 2	1.2	ACRE
25100120	MULCH, METHOD 2	2.0	TON
28000250	TEMPORARY EROSION CONTROL SEEDING	650	POUND
28000300	TEMPORARY DITCH CHECKS	10	EACH
28000400	PERIMETER EROSION BARRIER	300	FOOT
28000500	INLET AND PIPE PROTECTION	7	EACH
35100100	AGGREGATE BASE COURSE, TYPE A	1760	TON
35101400	AGGREGATE BASE COURSE, TYPE B	731	TON
40300100	BITUMINOUS MATERIALS (PRIME COAT)	2618	GALLON
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	5036	GALLON
40300600	SEAL COAT AGGREGATE	212	TON
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	220	TON

42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	3312	SQ FT
42400800	DETECTABLE WARNINGS	80	SQ FT
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	1967	SQ YD
44000600	SIDEWALK REMOVAL	6384	SQ FT
542D0213	PIPE CULVERTS, CLASS D, TYPE 1 8"	64	FOOT
542D0215	PIPE CULVERTS, CLASS D, TYPE 1 10"	48	FOOT
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	32	FOOT
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	38	FOOT
542D1087	PIPE CULVERTS, CLASS D, TYPE 2 42"	36	FOOT
54215550	METAL END SECTIONS 15"	2	EACH
54215559	METAL END SECTIONS 24"	2	EACH
54215577	METAL END SECTIONS 42"	2	EACH
66400105	CHAIN LINK FENCE, 4'	195	FOOT
66400805	CHAIN LINK GATES, 4'X5' SINGLE	1	EACH
67100100	MOBILIZATION	1.0	L SUM
72000100	SIGN PANEL- TYPE 1	36	SQ FT
78001110	* PAINT PAVEMENT MARKING - LINE 4"	1156	FOOT
78001130	* PAINT PAVEMENT MARKING - LINE 6"	100	FOOT
78001180	* PAINT PAVEMENT MARKING - LINE 24"	13.00	FOOT
78001300	* PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS, APPLIED	18.4	SQ FT

A2001016	* TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	7	EACH
B2001116	* TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	7	EACH
B2001316	* TREE, CORNUS FLORIDA (FLOWERING DOGWOOD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	7	EACH
X0350800	BOLLARDS	2	EACH
XX001011	BICYCLE RACKS	2	EACH
XX008010	FITNESS EQUIPMENT COMPLETE	1	L.SUM
XX0301430	PRECAST CONCRETE PARKING BLOCK	39	EACH
XX006785	TIMBER BICYCLE RAILING	1660	FOOT
XX008011	TIMBER RUB RAIL	400	FOOT
XX008012	WOODEN SIGN POST 4"X4"X10'	11	EACH
XX008013	WOODEN SIGN POST 4"X4"X12'	2	EACH

\* SPECIALTY ITEMS

**UTILITIES**

**POWER & GAS:** Ameren CIPS  
711 SOUTH 9<sup>TH</sup> STREET  
MATTOON ILLINOIS 61938

**TELEPHONE:** CONSOILDATED TELEPHONE COMPANY  
121 SOUTH 17<sup>TH</sup> STREET  
MATTOON ILLINOIS 61938

**WATER & SEWER:** CITY OF SHELBYVILLE ILLINOIS  
131 SOUTH MORGAN STREET  
SHELBYVILLE ILLINOIS 62565

**INDEX OF PAGES**

1. COVER SHEET
2. INDEX OF PAGES AND HIGHWAY STANDARDS, SUMMARY OF QUANTITIES AND UTILITIES
3. GENERAL NOTES & RATES OF APPLICATIONS
4. TYPICAL CROSS SECTIONS
5. TIMBER RAIL DETAILS
6. SIGN LOCATION PAGE
7. PARKING LOT DETAILS
8. SCHEDULES
9. PLAN SHEET
10. CURVE DETAILS & BENCHMARKS
- 11-13 PROFILE SHEETS
- 14-29 CROSS SECTION SHEETS

HIGHWAY STANDARDS	
STANDARD NUMBER	STANDARD NAME
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
424001-05	CURB RAMPS FOR SIDEWALK
542401-01	METAL END SECTION FOR PIPE CULVERT
664001-02	CHAIN LINK FENCE
701801-04	LANE CLOSURE + CROSSWALK AN SIDEWALK CLOUSRES
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
BLR - 21-8	TRAFFIC CONTROL DEVICES ON RURAL LOCAL HIGHWAYS

CITY OF SHELBYVILLE ILLINOIS  
GENERAL DACEY TRAIL  
PHASE 4