

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
DISTRICT 6**

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTION
- 5 SCHEDULE OF QUANTITIES
- 6 DETAILS

EXAMINED April 3<sup>rd</sup> 20 15

[Signature]  
ENGINEER OF OPERATIONS

EXAMINED April 3 20 15

[Signature]  
ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED April 3 20 15

[Signature]  
ENGINEER OF PROGRAM DEVELOPMENT

STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701101-04 OFF-ROAD OPERATIONS MULTILANE, 15' TO 24' FROM PAVEMENT EDGE
- 701106-02 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
- 701400-08 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401-09 LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-09 LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
- 701411-09 LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
- 701446-06 TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701901-04 TRAFFIC CONTROL DEVICES


GENERAL NOTES

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE MICROSURFACING AND WHEN THE ROADWAY WILL BE OPENED TO TRAFFIC.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS


THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

SHORT TERM PAVEMENT MARKINGS	10	FT /100FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.0003	TONS/SQ YD
MICROSURFACING, SINGLE PASS	20	POUNDS / SQ YD

**ONLY THE PASSING IS TO BE CLOSED FOR THE CENTERLINE WORK.** 

THE TEMPORARY PAVEMENT MARKING SHALL BE PLACED 3' OFF CENTERLINE IN DRIVING LANE PRIOR TO REMOVING EXISTING LINE.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATING TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

 REVISED 6-4-15

• D6 PAVT PRESERVATION 2015

FILE NAME :	USER NAME : branhama	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, STANDARDS</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\CONTRMINT_CAD\72H78-FAI 55 II 55 - 05	PAVT PRES 2015-SAND\PLANS\ALL SHEETS.dgn	DRAWN -	REVISED -						55	*	SANGAMON	6	2
Default	PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -		CONTRACT NO. 72H78				ILLINOIS FED. AID PROJECT				
	PLOT DATE : Apr-03-2015 10:48:04AM	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY	
				0005	RURAL
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUNDS	22,207	22,207	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50	
67100100	MOBILIZATION	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	16	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	14,096	14,096	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4701	4701	
78008320	POLYUREA PAVEMENT MARKING, TYPE II, LINE 5"	FOOT	35,210	35,210	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3524	3524	
<del>78300100</del>	<del>PAVEMENT MARKING REMOVAL</del>	<del>SQ FT</del>	<del>27740</del>	<del>27740</del>	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3524	3524	
X0326218	FIBER-MODIFIED ASPHALT CRACK SEALING	FOOT	148,033	148,033	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY	
				0005	RURAL
X7010410	SPEED DISPLAY TRAILER	CAL MO	2	2	
Z0063804	MICRO-SURFACING, SINGLE PASS, TYPE II, MIXTURE D	SQ YD	49,345	49,345	

\* SPECIALTY ITEM

⚠ REVISÉ 6-1-15 ⚠ REVISÉ 6-4-15

• 06 PAVT PRESERVATION 2015

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FILE NAME *	USER NAME * branhams	DESIGNED -	REVISED -
S:\CONTRM\MAINT_CAD\72H78-FAI 55 (1 55) - 05	PAVT PRES 2015-SANG\PLANS\ALL SHEETS.dgn	DRAWN -	REVISED -
Default	PLOT SCALE * 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE * Apr-03-2015 02:03:05PM	DATE -	REVISED -

SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
--------	-------	----	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		SANGAMON	6	3
CONTRACT NO. 72H78				
ILLINOIS FED. AID PROJECT				

MAINLINE										
LOCATION STA. TO STA.		LENGTH	PAVEMENT MARKING TAPE TYPE III 4"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II, 5"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	FIBER-MODIFIED ASPHALT CRACK SEALING	MICRO-SURFACING SINGLE PASS TYPE II MIXTURE D	BITUMINOUS MATERIALS (PRIME COAT)
		FT	FT	SO FT	FT	EACH	EACH	FT	SO YD	POUNDS
NORTHBOUND										
285+00.00	366+00.68	16201.36	1620	540	4050	405	405	16201	5400	2430
366+00.68	369+37.72	BRIDGE OMISSION								
369+37.72	514+51.60	29027.76	2904	967	7260	726	726	29028	9676	4355
514+51.60	517+28.60	BRIDGE OMISSION								
517+28.60	532+97.74	3138.28	316	105	790	80	80	3138	1046	471
532+97.74	549+76.71	1678.97	168	60	420	43	43	1679	560	252
549+76.71	552+36.38	BRIDGE OMISSION								
552+36.38	755+62.82	20326.44	2032	678	5080	508	508	20326	6775	3049
SOUTHBOUND										
285+00.00	367+29.80	16459.6	1648	549	4120	412	412	16460	5487	2469
367+29.80	370+72.90	BRIDGE OMISSION								
370+72.90	514+51.60	28757.4	2876	958	7190	719	719	28757	9586	4314
514+51.60	517+28.60	BRIDGE OMISSION								
517+28.60	532+97.74	3138.28	316	106	780	79	79	3138	1046	471
532+97.74	550+70.32	1772.58	180	60	440	44	44	1773	591	266
550+70.32	552+29.99	BRIDGE OMISSION								
552+29.99	755+62.82	20332.83	2036	678	5080	508	508	20333	6778	3050
I-55 AND EXIT 88		1800.00						1800	600	270
I-55 AND EXIT 83		1800.00						1800	600	270
I-55 AND EXIT 82		1800.00						1800	600	270
I-55 AND EXIT 80		1800.00						1800	600	270
TOTAL			14096	4701	35210	3524	3524	148033	49345	22207

2 REVISED SHEET 6-4-15

• 06 PAVT PRESERVATION 2015

FILE NAME =	USER NAME = branham	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\CONTRACTS\2015-2016\72H78-PAV 55 (1 55) - 05 PAVT PRES 2015-SANGAMON SHEETS.dgn	DRAWN -	REVISED -	55			-	SANGAMON	6	6	
PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -	CONTRACT NO. 72H78							
PLOT DATE = 6/3/2015	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
Default				SCALE:	SHEET OF SHEETS	STA.	TO STA.			