

90% FED
10% STATE

90% FED
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0047 SN 018-0042	0047 SN 018-0043
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	188	94	94
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	1613	807	806
40604114	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5FC, MIX "D", N90	TON	1067	533.5	533.5
40604164	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "D", N90	TON	120	60	60
42000060	WELDED WIRE REINFORCEMENT	SO YD	1613	807	806
42000070	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	SO YD	178	89	89
44000100	PAVEMENT REMOVAL	SO YD	178	89	89
44004250	PAVED SHOULDER REMOVAL	SO YD	1613	807	806
50102400	CONCRETE REMOVAL	CU YD	14.4	7.2	7.2
50300225	CONCRETE STRUCTURES	CU YD	54.8	27.4	27.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	16	8	8
50300300	PROTECTIVE COAT	SO YD	2266	1133	1133
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	233.2	116.6	116.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	91920	45960	45960

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0047 SN 018-0042	0047 SN 018-0043
50800515	BAR SPLICERS	EACH	616	308	308
52000110	PREFORMED JOINT STRIP SEAL	FOOT	168	84	84
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	1764	883	881
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6	3	3
70107007	PAVEMENT MARKING BLACKOUT TAPE, 7"	FOOT	1393	697	696
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	14	14
70300100	SHORT TERM PAVEMENT MARKING	FOOT	152	76	76
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	864	432	432
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1152	576	576

REV. 6-3-2020

FILE NAME =	USER NAME = steffennk	DESIGNED -	REVISED -
pw:\plnroom\dot.illinois.gov\PIDOT\Documents\IDOT Offices\District 7\Projects\74972\DRAWN\CADsheets\0774972-shr-S00.dgn		DRAWN	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 4/7/2020	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D7 BRIDGE REPAIRS 2020-6	CUMBERLAND	33	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74972	

WIDENING SCHEDULE

STATION TO STATION	PORTLAND CEMENT CONCRETE BASE COURSE, 10"	WELDED WIRE REINFORCEMENT	PAVED SHOULDER REMOVAL	SHOULDER RUMBLE STRIPS, 16"
	SQ YD	SQ YD	SQ YD	FOOT
EB				
256+44 TO 259+59	350.0	350.0	350.0	315.0
262+15 TO 263+92	196.7	196.7	196.7	177.0
257+45 TO 259+59	142.7	142.7	142.7	214.0
262+15 TO 263+92	118.0	118.0	118.0	177.0
EAST BOUND TOTALS	807.3	807.3	807.3	883.0
WB				
257+83 TO 259+59	195.6	195.6	195.6	176.0
262+15 TO 265+30	350.0	350.0	350.0	315.0
257+83 TO 259+59	117.3	117.3	117.3	176.0
262+15 TO 264+29	142.7	142.7	142.7	214.0
WEST BOUND TOTALS	805.6	805.6	805.6	881.0
TOTAL	1613	1613	1613	1764

PAVING SCHEDULE

LOCATION	SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	TON	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	PAVEMENT REMOVAL	APPROACH SLAB REMOVAL
	SQ YD		SQ YD	SQ YD	SQ YD
EASTBOUND					
WEST END	266.7	30	44.4	44.4	133.3
EAST END	266.7	30	44.4	44.4	133.3
EASTBOUND TOTALS	533.3	60	88.9	88.9	266.7
WESTBOUND					
WEST END	266.7	30	44.4	44.4	133.3
EAST END	266.7	30	44.4	44.4	133.3
WESTBOUND TOTALS	533.3	60	88.9	88.9	266.7
TOTAL	1067	120	178	178	534

POLYMERIZED HOT-MIX ASPHALT,
IL-9.5, MIX "D", N90



MODEL: Default
FILE NAME: P:\glennroom.dwt\illinois.gov\IWDOT\Documents\DOT_Offices\District_7\Projects\174972\CADD\DATA\CAD\Drawings\174972-shs-schedule.dgn

REV. 6-3-2020

USER NAME = steffemk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 4/7/2020	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	D-7 BRIDGE REPAIRS 2020-6	CUMBERLAND	33	6
			CONTRACT NO. 74972	
			ILLINOIS FED. AID PROJECT	