



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 27, 2020

SUBJECT: Route Heritage Trail
Section 10-00007-00-BT (Williamsville)
Sangamon County
Contract No. 93714
Item 209
June 12, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 8 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

- Model CBBR-2URI-BK
Belson Outdoors, LLC
627 Amersdale Drive
Naperville, IL 60563
(800) 323-5664
www.belson.com
- Model TP202U
Bikekeeper
8461 Lake Worth Road
Suite 173
Lake Worth, FL 33467
(561) 209-6863
www.bikekeeper.com

Delivery, Storage and Handling

1. All materials shall be transported and handled to avoid physical damage. At the site, materials shall be kept off the ground and covered to keep them dry.

Execution

1. Concrete pads at trail heads.
 - a. Locations shall be staked by the Engineer.
 - b. The area shall be excavated and surface compacted.
 - c. A base of CA-6 according to Article 1004.04 of the Standard Specifications shall be placed and compacted.
 - d. Concrete pads shall be constructed as specified in Section 424 of the Standard Specifications. Round openings shall be reserved for footings as shown on the plans. Surface shall slope to drain as shown on the plans. Edges shall be rounded over and surface shall be smooth.
2. Bicycle Racks.
 - a. At trail head locations, holes for footings shall be augered through openings left in concrete pads to the dimensions and depth shown on the plans.
 - b. At rest stop locations, holes shall be cut through HMA surface, soil augered out for footings to the dimensions shown on the plans. Cuts shall be clean and straight.
 - c. Bicycle racks shall be set straight and true and concrete footings constructed according to the plans. Bicycle racks shall be protected from splattering during concrete operations.
 - d. Any bicycle racks damaged during installation shall be replaced. Any minor abrasions shall be repaired with touch-up paint to the satisfaction of the Engineer.
3. Areas shall be left neat and clean.

This work shall be paid for at the contract unit price per EACH for BICYCLE RACKS, which shall include all labor, equipment and materials necessary for the completion of the work.