



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 28, 2026

SUBJECT FAP Route 339 (IL 62)
Project NHPP-2JQ7(624)
Section 2025-2009-RS
Cook County
Contract No. 80B28
Item No. 19, June 12, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page iii of the Table of Contents to the Special Provisions
3. Revised page 19 of the Special Provisions
4. Added page 172 to the Special Provisions
5. Revised sheets 1, 2, 6, 10, 48-50, 54, & 55 of the Plans
6. Added sheets 63A, 65A, & 65B to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

SIGN PANELS AND APPURTENANCES (BDE).....	151
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	153
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	154
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	155
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	155
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	156
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	158
SURVEYING SERVICES (BDE)	164
TRAINING SPECIAL PROVISIONS (BDE)	164
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	167
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	169
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	169
WORKING DAYS (BDE)	171
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	172

Revised 5/28/2026

701601	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSIBLE MEDIAN
701602	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701701	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901	TRAFFIC CONTROL DEVICES

DETAILS:

TC-08:	ENTRANCE AND EXIT RAMP CLOSURE DETAILS
TC-10:	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
TC-12:	MULTI-LANE FREEWAY PAVEMENT MARKING DETAIL
TC-13:	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
TC-14:	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
TC-16:	SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS
TC-17:	TRAFFIC CONTROL FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES
TC-22:	ARTERIAL ROAD INFORMATION SIGN
TC-26:	DRIVEWAY ENTRANCE SIGNING

SPECIAL PROVISIONS:

Maintenance of Roadways (D1)
Public Convenience and Safety (D1)
Keeping the Expressway Open to Traffic
Failure to Open Traffic Lanes to Traffic
Traffic Control and Protection (Expressways)
Temporary Information Signing
Traffic Control for Work Zone Areas
Keeping Arterial Roadways Open to Traffic (Lane Closures Only) (Four-Or-More Lane, Two Way)
Short Term and Temporary Pavement Markings (BDE)
Vehicle and Equipment Warning Lights (BDE)
Work Zone Traffic Control Devices (BDE)
Pavement and Shoulder Resurfacing
Work Restrictions

Revised 5/28/2026

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description: This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites: The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis: When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

IL 62 (Algonquin Road) from the Intersection of Radisson Way to the Intersection of Barker Avenue, Rolling Meadows / Schaumburg, Cook County

- All excavation planned for resurfacing, patching, median, guardrail, and ADA improvements along both sides of IL 62 (Algonquin Road) from the intersection of Radisson Way to the intersection of Barker Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None

Added 5/28/2026